

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
857	101BR-6	WHITE	100	7
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

PAVING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	SUB-BASE GRANULAR MATERIAL, TYPE A, 6"	SUB-BASE GRANULAR MATERIAL, TYPE A, 10"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	PAVEMENT REMOVAL	HOT MIX ASPHALT PAVEMENT (FULL DEPTH), 14"	HOT MIX ASPHALT SURFACE COURSE, MIX C, N50	HOT MIX ASPHALT BINDER COURSE, IL-19.0, N70	INCIDENTAL HOT MIX ASPHALT SURFACING	FLEXIBLE CONNECTOR	BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	DETOUR ROAD REMOVAL	PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	PAINT PAVEMENT MARKING-LINE 4"	
																							LIN FT
DETOUR																							
STA. 100+00.00 TO STA. 100+46.10	46.10	26	133																			103.72	
STA. 100+46.10 TO STA. 100+79.83	33.70	1	4		6		0.4					0.3	0.8									75.89	
STA. 100+79.83 TO STA. 102+23.80	144.00	VARIABLE	156		164		15.6					13.1	28.4									323.93	
STA. 102+23.80 TO STA. 107+23.00	499.21	22	1220		1276		122					102.5	222.1									1123.23	
BRIDGE OMISSION																							
STA. 108+43.01 TO STA. 119+94.40	1151.39	22	2815		2942		281.5					236.4	512.2									2475.38	
STA. 119+94.40 TO STA. 121+38.20	143.80	VARIABLE	156		164		15.6					13.1	28.4									323.7	
STA. 121+38.20 TO STA. 121+71.90	33.70	1	4		6		0.4					0.3	0.7									75.83	
STA. 121+71.90 TO STA. 122+18.12	46.22	26	134																			103.99	
IL 14																							
STA. 162+25.00 TO STA. 166+50.00	425.00	26	1228			102.22													204.19			956.25	
STA. 166+50.00 TO STA. 169+19.50	269.50	26	779			388.52	77.9	779				87.2		25								606.38	
STA. 169+19.50 TO STA. 169+25.50	6.00	33.33	22			10.00				20					22.22							13.50	
STA. 169+25.50 TO STA. 169+55.50	30.00	33.33	111			0.00				41						111	114					67.50	
BRIDGE OMISSION																							
STA. 173+61.50 TO STA. 173+91.50	30.00	33.33	111			0.00																913.05	
STA. 173+91.50 TO STA. 173+97.50	6.00	33.33	22			10.00									22.22		111	114				67.50	
STA. 173+97.50 TO STA. 179+50.00	552.50	26	1596	1801		899.02	159.6		174	1596												1243.13	
STA. 179+50.00 TO STA. 184+20.00	470.00	26	1358			115.56													204.19			1057.50	
DETOUR REMOVAL																							
STA. 100+00.00 TO STA. 100+46.10	46.10	26	133																			35	
STA. 100+46.10 TO STA. 100+79.83	33.70	1	4																			20	
STA. 100+79.83 TO STA. 102+23.80	144.00	VARIABLE	156																			55	
STA. 102+23.80 TO STA. 107+23.00	499.21	22	1220																			1220	
BRIDGE OMISSION																							
STA. 108+43.01 TO STA. 119+94.40	1151.39	22	2815																			2815	
STA. 119+94.40 TO STA. 121+38.20	143.80	VARIABLE	156																			156	
STA. 121+38.20 TO STA. 121+71.90	33.70	1	4																			4	
STA. 121+71.90 TO STA. 122+18.12	46.22	26	134																			34	
PROJECT TOTALS					1801	4557	1525	673	0	779	234	1596	453	793	25	44.44	222	228	4354	408.38	224	4876	4938

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVING SCHEDULE

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE

swartz-rw
 10/4/2006
 c:\projects\94675d\03897pa.dgn