

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			24	5
STA. TO STA.				
FED. ROAD DIST. NO. - ILLINOIS			FED. AID PROJECT	

- FAP 331 & FAP 776
- 10IRS-5; (114Z)RS-3
- JACKSON & HAMILTON

SUMMARY OF QUANTITIES

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAP 331 (IL 149)	FAP 776 (IL 142)
				JACKSON 100% STATE 1000 QUANTITY	HAMILTON 100% STATE 1000 QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	617	0	617
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1619	1619	0
40600300	AGGREGATE (PRIME COAT)	TON	37	27	10
40600990	TEMPORARY RAMP	SQ YD	247	38	209
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	576	0	576
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N105	TON	1511	1511	0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	24834	17979	6855
44201385	CLASS C PATCHES, TYPE I, 13 INCH	SQ YD	13	13	0
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SQ YD	150	136	14
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SQ YD	129	108	21
44201396	CLASS C PATCHES, TY IV, 13 INCH	SQ YD	634	234	400
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	828	660	168
70300210	TEMPORARY PAVEMENT MARKING, LETTERS ^{AND} SYMBOLS	SQ FT	541.6	400	141.6
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	9387	8492	895
70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	2213	1833	380
70300260	TEMPORARY PAVEMENT MARKING, LINE 12"	FOOT	170	150	20
70300280	TEMPORARY PAVEMENT MARKING, LINE 24"	FOOT	287	140	147
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5232	4882	350
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS ^{AND} SYMBOLS	SQ FT	541.6	400	141.6
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9387	8492	895
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2213	1833	380
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170	150	20
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	287	140	147
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	155	108	47

**SPECIALTY ITEMS*

PLOT DATE = 12/12/2005
 FILE NAME = s:\projects\1142\1142RS-3\1142RS-3.dwg
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = mcorbett