

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			24	9
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

- FAP 331 & FAP 776
- 10IRS-5; (114Z)RS-3
- JACKSON & HAMILTON

MAINLINE RESURFACING SCHEDULE

LOCATION STATION TO STATION	LENGTH	ROADWAY WIDTH	ROADWAY AREA	HOT-MIX ASPH. SURF. REM. 1 1/2"	TEMPORARY RAMP	POLY. HOT-MIX ASPHALT S. C., MIX. D, N105	HOT-MIX ASPHALT S. C., MIX C, N 90	POLY. BIT. MATL. PR. CT	BIT. MATL. PRIME COAT	AGG. PRIME COAT											
											FOR INFORMATIONAL PURPOSE ONLY										
											FT	FT	SQ YD	SO YD	SO YD	TON	TON	GAL	GAL	TON	
FAP 331(Murphysboro) - Sta. 13+00 to Sta. 55+62																					
11th St. to 17th St.	13+00.00	TO	33+10.00	2010.0	30.0	6700	6700	16.7	563	603.0	10.0										
17th St. to 22nd St.	33+10.00	TO	55+62.00	2252.0	38.0	9508	9508	21.1	799	856.0	14.3										
Subtotal - FAP 331				4262.0		16,208	16,208	38.0	1362	0	1,459.0	0.0	24.3								
FAP 776 (McLeansboro) - 3 Legs of Square																					
Washington St.	14+62	TO	15+40			615	615	25.0		52	55.4	0.9									
Market St.	200+50	TO	204+80	430.0	45.0	2372	2372	17.0	199		213.5	3.6									
Market St.	Lt. 204+41							30.0													
N. Washington St.	118+15							34.0													
Washington St.	15+40	TO	18+65	325.0	45.0	1620	1624	33.9		136	145.8	2.4									
Jackson St.	204+84	TO	208+84	400.0	45.0	2244	2244	26.0		189	202.0	3.4									
Jackson St.	Lt. 208+69							15.0													
Main St. (EBL)								13.0													
Main St. (Lt. Turn)								15.0													
SUBTOTAL - FAP 776				755.0		6,851	6,855	209.0	0	576	0.0	617	10.3								
TOTALS							23,063	247	1362	576	1,459	617	34.6								

PARKING LANE RESURFACING SCHEDULE (MURPHYSBORO ONLY)

LOCATION STATION TO STATION	LENGTH	PARKING LN WIDTH	ROADWAY AREA	HOT-MIX ASP. SURF. REM. 1 1/2"	POLY. HOT-MIX ASP. S. C., SUPER. MIX. D, N105	HOT-MIX ASP. S. C., SUPER. MIX C, N 90	POLY. BIT. MATL. PRIME COAT	BIT. MATL. PRIME COAT	AGG. PRIME COAT										
										FOR INFORMATIONAL PURPOSE ONLY									
										FT	FT	SO YD	SO YD	TON	TON	GAL	GAL	TON	
FAP 331(Murphysboro) - Sta. 13+00 to Sta. 55+62																			
Right	13+53.00	TO	14+88.00	135.0	8.0	120.0	120.0	10.1		10.8	0.18								
Right	15+39.00	TO	16+73.00	134.0	8.0	119.1	119.1	10.0		10.7	0.18								
Right	17+30.00	TO	21+09.00	379.0	8.0	336.9	336.9	28.3		30.3	0.51								
Right	21+61.00	TO	24+83.00	322.0	8.0	286.2	286.2	24.0		25.8	0.43								
Right	25+30.00	TO	30+72.00	542.0	8.0	481.8	481.8	40.5		43.4	0.72								
Left	26+74.00	TO	28+48.00	174.0	8.0	154.7	154.7	13.0		13.9	0.23								
Left	28+96.00	TO	32+02.00	306.0	8.0	272.0	272.0	22.8		24.5	0.41								
TOTAL - FAP 331				1686.0		1,771	1,771	149.0	0.0	160.0	0.0	2.7							

PLOT DATE = 12/12/2005
 FILE NAME = c:\pca\pca\p980207\p980207.plt
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mccordr