





REVISIONS

NUMBER	BY	DATE



GATE 21 REMOVAL NOTES

- 1) REMOVE GATE OPERATOR AND DISPOSE OF OFFSITE.
- 2) REMOVE GATE OPERATOR FOUNDATION AND DISPOSE OF OFFSITE.
- 3) REMOVE ALL CONDUIT TO 1 FOOT (1') MINIMUM BELOW GRADE.
- 4) DISCONNECT AND REMOVE BOTH PROXIMITY CARD READERS AND TURN OVER TO THE AIRPORT.
- 5) REMOVE CARD READER POSTS AND FOUNDATIONS AND DISPOSE OF OFFSITE.
- 6) DISCONNECT AND REMOVE WIRELESS READER INTERFACE, POWER SUPPLY AND ANTENNA AND TURN OVER TO THE AIRPORT.
- 7) REMOVE ANTENNA MAST AND FOUNDATION AND DISPOSE OF OFFSITE.
- 8) RESTORE DISTURBED EARTH, LANDSCAPE, SEED, PROTECT AND FERTILIZE PER SPECIFICATIONS.

**BLOOMINGTON-NORMAL AIRPORT AUTHORITY
 CENTRAL ILLINOIS REGIONAL AIRPORT
 BLOOMINGTON, ILLINOIS**

**UPGRADE PERIMETER FENCE PHASE 1
 EXISTING GATE 21 REMOVALS**

© copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 94-000618



DESIGN BY:	CBG
DRAWN BY:	CMT
CHECKED BY:	<i>REN</i>
APPROVED BY:	<i>REN</i>
DATE:	1/12/2007
JOB No:	06085-03-00
ILLINOIS PROJECT BMI-3653	
A.I.P. PROJECT 3-17-0006-47	
SHEET 21 OF 26 SHEETS	