

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**  
 District 9  
 Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	9-01	State I. D. No.:	9S100I057L044.6		
County:	Williamson	Route:	I-57	M. P.:	44.6
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure Span	Each	1.00			
Overhead Sign Structure Span Type II-A	Foot	112.00			
Overhead Sign Structure Walkway	Foot	55.00			
Remove Concrete Foundation - Overhead	Each	2.00			
Drilled Shaft Concrete Foundation	Cu Yd	24.60			
Electric Service Disconnect	Each	1.00			
Sign Panel - Type 3	SQ FT	372.00			
Rock Excavation For Structures	Cu Yd	2.00			
Steel Plate Beam Guardrail, Type A, 6 Foot Posts	Foot	962.50			
Traffic Barrier Terminal, Type 2	Each	3.00			
Traffic Barrier Terminal, Type 1 (Special)Tangent	Each	3.00			
Terminal Marker-Direct Applied	Each	3.00			
Guardrail Markers, Type B	Each	14.00			

Location No.:	9-02	State I. D. No.:	9S100I057L044.9		
County:	Williamson	Route:	I-57	M. P.:	44.9
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure Span	Each	1.00			
Overhead Sign Structure Span Type II-A	Foot	88.00			
Overhead Sign Structure Walkway	Foot	32.00			
Remove Concrete Foundation - Overhead	Each	2.00			
Drilled Shaft Concrete Foundation	Cu Yd	21.50			
Electric Service Disconnect	Each	1.00			
Sign Panel - Type 3	SQ FT	270.00			
Rock Excavation For Structures	Cu Yd	4.00			
Steel Plate Beam Guardrail, Type A, 6 Foot Posts	Foot	962.50			
Traffic Barrier Terminal, Type 2	Each	3.00			
Traffic Barrier Terminal, Type 1 (Special)Tangent	Each	3.00			
Terminal Marker-Direct Applied	Each	3.00			
Guardrail Markers, Type B	Each	14.00			

Location No.:	9-03	State I. D. No.:	9C028I057R073.8		
County:	Franklin	Route:	I-57	M. P.:	73.8
Direction:	NB				
Description of Work	Unit	Quantity			
Overhead Sign Support Grout Repair	Each	4.00			

Location No.:	9-04	State I. D. No.:	9S028I057L078.8		
County:	Franklin	Route:	I-57	M. P.:	78.8
Direction:	SB				
Description of Work	Unit	Quantity			
Overhead Sign Support Grout Repair	Each	4.00			

Location No.:	9-05	State I. D. No.:	9C091I057R024.6		
County:	Union	Route:	I 57	M. P.:	24.6
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish and Install Internal Member Truss Clamp	Each	4.00			

Location No.:	9-06	State I. D. No.:	9S100I057R043.4		
County:	Williamson	Route:	I 57	M. P.:	43.4
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish and Install Internal Member Truss Clamp	Each	2.00			

Location No.:	9-07	State I. D. No.:	9S041I057R090.9		
County:	Jefferson	Route:	I-57	M. P.:	90.9
Direction:	NB				
Description of Work	Unit	Quantity			
Overhead Sign Support Grout Repair	Each	4.00			
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00			
Paint Overhead Sign Support	Each	2.00			

Location No.:	9-08	State I. D. No.:	9S041I057L097.5		
County:	Jefferson	Route:	I 57	M. P.:	97.5
Direction:	SB				
Description of Work	Unit	Quantity			
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00			

Location No.:	9-09	State I. D. No.:	9S041I064R072.9		
County:	Jefferson	Route:	I 64	M. P.:	72.9
Direction:	EB				
Description of Work	Unit	Quantity			
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00			
Overhead Sign Support Grout Repair	Each	4.00			

Location No.:	9-10	State I. D. No.:	9S041I064L078.5		
County:	Jefferson	Route:	I 64	M. P.:	78.5
Direction:	WB				
Description of Work	Unit	Quantity			
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00			

Location No.:	9-11	State I. D. No.:	9S041I064L078.9		
County:	Jefferson	Route:	I 64	M. P.:	78.9
Direction:	WB				
Description of Work	Unit	Quantity			
Repair Concrete Foundation for Overhead Sign Structure	Each	2.00			

**GUARDRAIL SCHEDULE**

LOCATION STA TO STA	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	GUARDRAIL MARKERS, TYPE B	TERMINAL MARKER - DIRECT APPLIED
	FOOT	EACH	EACH	EACH	EACH
<b>I 57</b>					
SBL					
LT STA 368+61.9 TO STA 369+11.9 (MEDIAN SIDE)			1.0		1.0
LT STA 369+11.9 TO STA 372+49.4 (MEDIAN SIDE)	337.5			5.0	
LT STA 372+49.4 TO STA 372+63.7 (MEDIAN SIDE)		1.0			
RT STA 369+20.6 TO STA 369+70.6 (OUTSIDE)			1.0		1.0
RT STA 369+70.6 TO STA 372+45.6 (OUTSIDE)	275.0			4.0	
RT STA 372+45.6 TO STA 372+62.9 (OUTSIDE)		1.0			
LT STA 385+01.9 TO STA 385+51.9 (MEDIAN SIDE)			1.0		1.0
LT STA 385+51.9 TO STA 388+89.4 (MEDIAN SIDE)	337.5			5.0	
LT STA 388+89.4 TO STA 389+03.7 (MEDIAN SIDE)		1.0			
RT STA 385+60.6 TO STA 386+10.6 (OUTSIDE)			1.0		1.0
RT STA 386+10.6 TO STA 388+85.6 (OUTSIDE)	275.0			4.0	
RT STA 388+85.6 TO STA 389+02.9 (OUTSIDE)		1.0			
<b>NBL</b>					
RT STA 372+53.7 TO STA 372+68. (MEDIAN SIDE)		1.0			
RT STA 372+68. TO STA 376+18. (MEDIAN SIDE)	350.0			5.0	
RT STA 376+18. TO STA 376+68. (MEDIAN SIDE)			1.0		1.0
RT STA 388+93.7 TO STA 389+08. (MEDIAN SIDE)		1.0			
RT STA 389+08. TO STA 392+58. (MEDIAN SIDE)	350.0			5.0	
RT STA 392+58. TO STA 393+08. (MEDIAN SIDE)			1.0		1.0
<b>PROJECT TOTAL</b>	<b>1,925.0</b>	<b>6.0</b>	<b>6.0</b>	<b>28.0</b>	<b>6.0</b>

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		CHECKED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Various	D-9 OVD SIN STR REPL 12-12	Various	17	4
			CONTRACT NO. 46185	
(ILLINOIS) FED. AID PROJECT				