

SUMMARY OF QUANTITIES

90% FED / 10% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	71	71
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,752	3,752
25000210	SEEDING, CLASS 2A	ACRE	0.65	0.65
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	66	66
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	66	66
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	66	66
25200110	SODDING, SALT TOLERANT	SQ YD	604	604
25100630	EROSION CONTROL BLANKET	SQ YD	3,148	3,148
42001300	PROTECTIVE COAT	SQ YD	379	379
44000100	PAVEMENT REMOVAL	SQ YD	3	3
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	5,087	5,087
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	700	700
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	85	85
63200310	GUARDRAIL REMOVAL	FOOT	4,584	4,584
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
78200420	GUARDRAIL MARKERS, TYPE B	EACH	137	137
78201000	TERMINAL MARKER DIRECT APPLIED	EACH	85	85
X2503100	MOWING	UNIT	283	283
Z0004562	COMBINATION CONCRETE CURB & GUTTER, REMOVAL & REPLACEMENT	FOOT	1,137	1,137
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206

\* DENOTES SPECIALTY ITEM

A 100% - 90% (10% STATE)