

11/20/11 07:54:50

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	RTE 1 OVER IC RR (ABANDONED) SN 016-2859	
				0005	0011	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	114	114	-	
20800150	TRENCH BACKFILL	CU YD	5	5	-	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	215	215	-	
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1	-	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12	-	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	12	-	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12	-	
25100630	EROSION CONTROL BLANKET	SO YD	276	276	-	
25200110	SODDING, SALT TOLERANT	SO YD	215	215	-	
28000400	PERIMETER EROSION BARRIER	FOOT	259	259	-	
28000510	INLET FILTERS	EACH	8	8	-	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	47	47	-	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	3	3	-	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6	0.6	-	
40600300	AGGREGATE (PRIME COAT)	TON	2.9	2.9	-	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2.1	2.1	-	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	59	59	-	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	64	64	-	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	5.5	5.5	-	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	147	147	-	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	112	112	-	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	32	32	-	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	3345	3345	-	
44000100	PAVEMENT REMOVAL	SO YD	86	86	-	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	1429	1429	-	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	78	78	-	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	562	562	-	
44000600	SIDEWALK REMOVAL	SO FT	1935	1935	-	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	-	1	
50102400	CONCRETE REMOVAL	CU YD	39.8	-	39.8	
50200100	STRUCTURE EXCAVATION	CU YD	290	-	290	
50300225	CONCRETE STRUCTURES	CU YD	95.1	-	95.1	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	RTE 1 OVER IC RR (ABANDONED) SN 016-2859	
				0005	0011	
50300255	CONCRETE SUPERSTRUCTURES	CU YD	434.7	-	434.7	
50300260	BRIDGE DECK GROOVING	SO YD	257	-	257	
50300300	PROTECTIVE COAT	SO YD	896	639	257	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	14860	-	14860	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	112,340	-	112,340	
50800515	BAR SPLICERS	EACH	344	-	344	
50900105	ALUMINUM RAILING, TYPE L	FOOT	68	-	68	
51100100	SLOPE WALL 4 INCH	SO YD	122	-	122	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1196	-	1196	
51202305	DRIVING PILES	FOOT	1196	-	1196	
51203600	TEST PILE STEEL HP12X53	EACH	2	-	2	
51500100	NAME PLATES	EACH	1	-	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	16	16	-	
56109210	WATER VALVES TO BE ADJUSTED	EACH	1	1	-	
59000200	EPOXY CRACK INJECTION	FOOT	198	-	198	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	56	-	56	
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	2	2	-	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4	-	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2	-	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	444	444	-	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	-	
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1	-	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3	-	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	-	
63200310	GUARDRAIL REMOVAL	FOOT	370	370	-	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	-	
67100100	MOBILIZATION	L SUM	1	1	-	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	324	324	-	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2553	2553	-	
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	4423	4423	-	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2380	2380	-	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	367	367	-	

\* SPECIALTY ITEM

FILE NAME: P:\2007\ME07080\_Ver-Var-Phi\1\Cadd\W038\_IL\_Rt1\Shets\03-04-D160P38-sht-S00.dgn  
 USER NAME: Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.8110 voice, 630.839.2566 fax  
 www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	12/14/2011	REVISED	-

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 1 (HALSTED ST)**  
**OVER IC RR (ABANDONED) (SN 016-2859)**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	2011-032-BR	COOK	41	3
CONTRACT NO. 60P38			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: NTS    SHEET NO. 1 OF 2 SHEETS    STA.    TO STA.

P:\2007\ME07080\_Ver-Var-Phi\1\Cadd\W038\_IL\_Rt1\Shets\03-04-D160P38-sht-S00.dgn