

SUMMARY OF QUANTITIES

| CODED PAY ITEM NUMBER | PAY ITEM | UNIT | TOTAL QUANTITIES | 801 FED./201 STATE URBAN CONSTRUCTION TYPE CODE | |
|-----------------------|--|--------|------------------|--|---------------------------------|
| | | | | ROADWAY 0004 | BRIDGE REHABILITATION 0014 0040 |
| 20200100 | EARTH EXCAVATION | CU YD | 50 | 50 | |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 168 | | 168 |
| 28200200 | FILTER FABRIC | SQ YD | 168 | | 168 |
| 31101400 | SUBBASE GRANULAR MATERIAL, TYPE B 6" | SQ YD | 16 | 16 | |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SQ YD | 22 | 22 | |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 10 | 10 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 1 | 1 | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 3 | 3 | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 8 | 8 | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 22 | 22 | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SQ YD | 16 | 16 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 25.0 | | 25.0 |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 261 | | 261 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 40.0 | | 40.0 |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 380 | | 380 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 8080 | | 8080 |
| 54003000 | CONCRETE BOX CULVERTS | CU YD | 15.4 | | 15.4 |
| 64200116 | SHOULDER RUMBLE STRIPS, 16 INCH | FOOT | 432 | 432 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 85 | 85 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 2 | 2 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 680 | 680 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 100.0 | 100.0 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 2020 | 2020 | |

* INDICATES SPECIALTY ITEMS

| CODED PAY ITEM NUMBER | PAY ITEM | UNIT | TOTAL QUANTITIES | 801 FED./201 STATE URBAN CONSTRUCTION TYPE CODE | |
|-----------------------|---|-------|------------------|--|---------------------------------|
| | | | | ROADWAY 0004 | BRIDGE REHABILITATION 0014 0040 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 14 | 14 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 674 | 674 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 14 | 14 | |
| X0325201 | SHOULDER RUMBLE STRIP REMOVAL | SQ YD | 60 | 60 | |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 | |
| X7030030 | WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH | FOOT | 2040 | 2040 | |
| Z0001903 | STRUCTURAL STEEL REMOVAL | POUND | 5010 | | 5010 |
| Z0007122 | REMOVING AND RE-ERECTING EXISTING RAILING | FOOT | 60 | | 60 |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | |
| Z0015500 | DEBRIS REMOVAL | L SUM | 1 | | 1 |
| Z0026407 | TEMPORARY SHEET PILING | SQ FT | 1802 | | 1802 |
| Z0030290 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| Z0030890 | TEMPORARY INFORMATION SIGNING | SQ FT | 52 | 52 | |
| Z0062496 | TEMPORARY PAVEMENT | SQ YD | 204 | 204 | |

* INDICATES SPECIALTY ITEMS