

SUMMARY OF QUANTITIES

URBAN

90% FED / 10% STATE

90% / 6-7 / 3-3 /

Fed / State / City

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY	0021 SIGNAL AT THORNTON RD	0021 SIGNAL AT 138th ST	0021 SIGNAL AT BROADWAY ST
20100500	TREE REMOVAL, ACRES	ACRE	0.10	0.10			
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	8.56	8.56			
20800150	TRENCH BACKFILL	CU YD	4,454	4,454			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,732	5,732			
21400100	GRADING AND SHAPING DITCHES	FOOT	3,567	3,567			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	71	71			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	71	71			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	71	71			
25200110	SODDING, SALT TOLERANT	SQ YD	5,732	5,732			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9	9			
28000400	PERIMETER EROSION BARRIER	FOOT	425	425			
28100107	STONE RIPRAP, CLASS A4	SQ YD	41	41			
28200200	FILTER FABRIC	SQ YD	41	41			
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SQ YD	222	222			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	107	107			
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	79	79			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28			
40600300	AGGREGATE (PRIME COAT)	TON	138	138			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52	52			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,449	1,449			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	362	362			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12	12			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,897	2,897			
42001300	PROTECTIVE COAT	SQ YD	2223	2223			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3449	3449			
42400800	DETECTABLE WARNINGS	SQ FT	16	16			
44000100	PAVEMENT REMOVAL	SQ YD	326	326			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	34,189	34,189			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	107	107			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4489	4489			
44000600	SIDEWALK REMOVAL	SQ FT	3,833	3,833			
44003100	MEDIAN REMOVAL	SQ FT	1715	1715			
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	57	57			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	27	27			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	82	82			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	60	60			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1,881	1,881			
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	352	352			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	209	209			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	469	469			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1			
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	20	20			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	56	56			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2			
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2			
54215550	METAL END SECTIONS 15"	EACH	4	4			
54244405	FLUSH INLET BOX FOR MEDIAMETER, STANDARD 542546	EACH	3	3			
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	2	2			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,307	1,307			

* DENOTES SPECIALTY ITEM

FILE NAME =
FILE

USER NAME = .USER.
PLOT SCALE = 50' / IN.
PLOT DATE = 12/28/2011

DESIGNED - EF
DRAWN - EF
CHECKED - RS
DATE - 12-28-2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ASHLAND AVE. (THORNTON RD. - BROADWAY ST.)
SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2857	2011-054-1	COOK	81	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P64	