CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY (100% STATE URBAN)	0014 STRUCTURE	0021 ROADWAY
20700220	POROUS GRANULAR EMBANKMENT	CU YD	278	278	
42100200	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	195	195	
42100615	PAVEMENT REINFORCEMENT	SQ YD	195	195	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	597	597	
44000100	PAVEMENT REMOVAL	SQ YD	195	195	
44000600	SIDEWALK REMOVAL	SQ FT	597	597	
50102400	CONCRETE REMOVAL	CU YD	144.7	144.7	
50200100	STRUCTURE EXCAVATION	CU YD	266	266	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	133.1	133.1	
50300300	PROTECTIVE COAT	SQ YD	329	329	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14,070	14,070	
50800530	MECHANICAL SPLICERS	EACH	609	609	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3
67100100	MOBILIZATION	L SUM	1		1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10		10
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8		8
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	683		683
70400100	TEMPORARY CONCRETE BARRIER	FOOT	675.0		675.0
* 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5		362.5
~~* 78000200~~	~~THERMOPLASTIC PAVEMENT MARKING - LINE 4"~~	~~FOOT~~	~~171~~		~~171~~
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1177		1177
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20		20
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12		12
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	108		108
78300100	PAVEMENT MARKING REMOVAL	SQ FT	394		394
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32		32
X5810100	WATERPROOFING MEMBRANE SYSTEM (SPECIAL)	SQ YD	86	86	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		1
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	2048		2048
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2
Z0030332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	150		150
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0014 STRUCTURE	0005 ROADWAY

* DENOTES SPECIALTY ITEM

Rev.

LIN ENGINEERING, LTD.
Consulting Engineers
Springfield, Illinois

USER NAME = $USER$	DESIGNED - SEW	REVISED -	
	DRAWN - RK	REVISED -	
PLOT SCALE = $SCALE$	CHECKED - SEW	REVISED -	
PLOT DATE = $DATE$	DATE - 1/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.I. 90 (I-90) AT ILL 50 (CICERO AVENUE)

SCALE: N/A | SHEET NO. 1 OF 1 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2011-063-I	COOK	18	3

CONTRACT NO. 60P82

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT