

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE 0014				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE				
42101300	PROTECTIVE COAT	SQ YD	2296	2296				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	220	220				
44000600	SIDEWALK REMOVAL	SQ FT	220	220				
50102400	CONCRETE REMOVAL	CU YD	9.4	9.4				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.4	9.4				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3342	3342				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1090	1090				
50800515	BAR SPLICERS	EACH	16	16				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	230	230				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	12				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12				
52100520	ANCHOR BOLTS, 1"	EACH	48	48				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	806	806				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2723	2723				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	910	910				
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	2416	2416				
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24				
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	75	75				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	155	155				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

\*Specialty Items

FILE NAME =	USER NAME = curryw	DESIGNED AWC	REVISED -
c:\pw\work\pav\tdofcurryw\02282133\062011-shr-pln.dgn		DRAWN AWC	REVISED -
PLOT SCALE = 39335487' / 1 m		CHECKED -	REVISED -
PLOT DATE = 1/9/2012		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2011-064-1	COOK	30	3
CONTRACT NO. 60P83				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.