



NOTE:
 Remove and replace existing diaphragm and channel clip angles with a W 12X26 and MC 10X21.9 respectively. The cost is included in Structural Steel Repair.

BILL OF MATERIALS

ITEM	UNIT	QUANTITY
STRUCTURAL STEEL REPAIR	POUND	240

FILE NAME =	USER NAME = curryw	DESIGNED - ARP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	39TH ST. (PERSHING RD) OVER RACINE AVE (SN 016-0396) STRUCTURAL STEEL REPAIR	P.A.I. RTE. 90/94	SECTION 2011-068-BR	COUNTY COOK	TOTAL SHEETS 21	SHEET NO. 5	
or\pwwork\pwwdot\curryw\ad283496\016211-eh1-plan.dgn	PLOT SCALE = 3/4" = 1'-0"	DRAWN - ARP	REVISED -			SCALE:	SHEET NO. 2 OF 7 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60P87	
	PLOT DATE = 1/19/2012	CHECKED - AM	REVISED -								
		DATE - 12/22/11	REVISED -								