

CODE	ITEM	UNIT	URBAN	90% FED./10% STATE
			QTY.	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	37	37
20400800	FURNISHED EXCAVATION	CU YD	182	182
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1236	1236
25000210	SEEDING, CLASS 2A	ACRE	0.3	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27
25100630	EROSION CONTROL BLANKET	SQ YD	1236	1236
44000300	CURB REMOVAL	FOOT	39	39
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1514	1514
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	1113	1113
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	250	250
50102400	CONCRETE REMOVAL	CU YD	25	25
50104000	BRIDGE RAIL REMOVAL	FOOT	129	129
50300255	CONCRETE SUPERSTRUCTURE	CU YD	56	56
50300300	PROTECTIVE COAT	SQ YD	230	230
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10440	10440
60600605	CONCRETE CURB, TYPE B	FOOT	77	77
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	389	389
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	212	212
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	361	361
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	553	553
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	612.5	612.5
63000017	STEEL PLATE BEAM GUARDRAIL, TYPE D, 6 FOOT POSTS	FOOT	250	250
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	27	27
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	13	13
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	2935	2935
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	4	4
64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	10	10
64301090	ATTENUATOR BASE	SQ YD	108	108
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3	3
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
78200410	GUARDRAIL MARKERS, TYPE A	EACH	71	71
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	19	19
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	27	27
X2503100	MOWING	UNIT	37	37
X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	500	500
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	360	360
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	1	1
Z0076600	TRAINEES	HOUR		

△ Non-participating - 100% State



USER NAME = #USER#	DESIGNED - GRE	REVISED -
	DRAWN - GRE	REVISED -
PLOT SCALE = #SCALE#	CHECKED - ST	REVISED -
PLOT DATE = #DATE#	DATE - 12/20/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GUARDRAIL IMPROVEMENTS - COOK COUNTY
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2011-093-GRR	COOK	26	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60R21	

*VARIOUS