

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY RE-CONSTRUCTION	RETAINING WALLS	LANDSCAPING ITEMS	TRAFFIC SIGNALS		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY RE-CONSTRUCTION	RETAINING WALLS	LANDSCAPING ITEMS	TRAFFIC SIGNALS	
				0004	0040	0004 0031	95TH ST. & 104TH AVE./FLAVIN RD. 0021	100% COST TO NORTH PALOS FIRE PROTECTION DISTRICT 0021					0004	0040	0004 0031	0021	0021
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	149	149					*87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	56					56
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	198	198					*88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3					3
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	15	15					*88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3					3
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3					*88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5					5
78300100	PAVEMENT MARKING REMOVAL	SO FT	3143	3143					*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8					8
*80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1				1		*88500100	INDUCTIVE LOOP DETECTOR	EACH	8					8
*81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	52				52		*88600100	DETECTOR LOOP, TYPE I	FOOT	1083					1083
*81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	317				317		*88700200	LIGHT DETECTOR	EACH	2					2
*81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	815				815		*88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1
*81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	40				40		*A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4			4		
*81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	363				363		*C2C01120	SHRUB, CEPHALANTHUS OCCIDENTALIS (BUTTON BUSH), 2' HEIGHT, CONTAINER	EACH	160			160		
*81400100	HANDHOLE	EACH	2				2		*K0013030	PERENNIAL PLANTS, WETLAND TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	6.08			6.08		
*81400200	HEAVY-DUTY HANDHOLE	EACH	7				7		*K0026850	PERENNIAL PLANT CARE	SO YD	264			264		
*81400300	DOUBLE HANDHOLE	EACH	1				1		*K0029626	WEED CONTROL, TEASEL	POUND	0.25			0.25		
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	590				590		*K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	400			400		
*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1	340	K1005418	TEMPORARY SEEDING	ACRE	3			3		
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	340						*KK029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL (WETLAND)	GALLON	4			4		
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	668				668		XX008455	INLET BOX, SPECIAL	EACH	1	1				
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1913				1913		XX006746	RUSTIFICATION FINISH, TYPE 1	SO FT	7140		7140			
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1707				1707		X0322992	COARSE SAND PLACEMENT, 4"	SO YD	70			70		
*87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	54				54		X2020110	GRADING AND SHAPING SHOULDERS	UNIT	62	62				
*87301900	ELECTRICAL CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	722				722		*X2501800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.3			0.3		
*87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1				1		*X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.4			0.4		
*87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1		X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2				
*87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1				1		X4400110	TEMPORARY PAVEMENT REMOVAL	SO YD	17625	17625				
*87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1				1		X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	1901	1901				
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12				12		X5121800	PERMANENT STEEL SHEET PILING	SO FT	7460		7460			
*87800200	CONCRETE FOUNDATION, TYPE B	FOOT	4				4		X6310176	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	3	3				
									X6640300	CHAIN LINK FENCE REMOVAL	FOOT	535	535				
									X6640560	CHAIN LINK FENCE, 6' (SPECIAL)	FOOT	535	535				

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

FILE NAME =	USER NAME = sreedpa	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES 95th STREET @ 104th AVENUE/ FLAVIN ROAD				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cdw_work\p\tdof\stee\pa\0159915\144499-Design.dwg	DRAWN	REVISED	REVISED									1566	29R-N-1	COOK	120	5
PLOT SCALE = 50.0000' / 1"	CHECKED	REVISED	REVISED									CONTRACT NO. 62377				
PLOT DATE = 12/15/2011	DATE	REVISED	REVISED									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.						