F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				

WEBER ROAD AT RENWICK ROAD INTERSECTION IMPROVEMENT

SP	SI	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
						STA 0003	STP 0003	STA TRAFFIC SIGNALS 0021	TRAINEES 0042
		60600605	CONCRETE CURB, TYPE B	FOOT	144		144		
		60603800	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	FOOT	1,057		1,057		
		60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FOOT	23,766		23,766		
		60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	2,016		2,016		
		60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	3,714		3,714		
*		60623800	CONCRETE BARRIER MEDIAN	SQ FT	5,457		5,457		
		60624600	CORRUGATED MEDIAN	SQ FT	2,992		2,992		
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12		
		67100100	MOBILIZATION	L SUM	1		1		
		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	365		365		
*		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	48		48		
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	944		944		
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	63,220		63,220		
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	258		258		
		70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	472		472		
		70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	73,742		73,742		
		70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	299		299		
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	46,523		46,523		
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	3,742		3,742		
		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	394		394		
	+	72000100	SIGN PANEL - TYPE 1	SQ FT	510		510		
		72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5		5		
		72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5		5		
	+	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5		5		
	+	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	5		5		
	+	72900100	METAL POST - TYPE A	FOOT	405		405		
	+	72900200	METAL POST - TYPE B	FOOT	330		330		
	+	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	489		489		
	+	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,293		17,293		
	+	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	158		158		
	+	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,500		1,500		
	+	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	114		114		
	+	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1,784		1,784		
	+	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	13,071		13,071		
	+	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	8,642		8,642		
	+	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1,295		1,295		
	+	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	590		590		
	+	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,157		1,157		
		78300100	PAVEMENT MARKING REMOVAL	SQ FT	14,000		14,000		
		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,200		1,200		
*	+	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1		
*	+	80400200	ELECTRIC UTILITY SERVICE CONNECTION (COM ED)	L SUM	1		1		
	+	80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2			2	
	+	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4,093			4,093	
	+	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	85			85	
	+	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	861		711	150	

* SPECIAL PROVISION, PLAN NOTE, OR DETAIL HAS BEEN PROVIDED.

\+ SPECIALITY ITEM.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEBER ROAD AND RENWICK ROAD
SUMMARY OF QUANTITIES

SCALE: DRAWN BY CJO

DATE APRIL, 2011 CHECKED BY MFB

11/1/2011
P:\79766\cadd\drawings\006SumQuant.dgn