| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 856 | 01-00170-26-TL | WILL | 171 | 78 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |
| CONTRACT NO: 63570 | | | | |

## RENWICK ROAD DRAINAGE PIPE SCHEDULE - WEST LEG (CTD.)

| PIPE NO. | PIPE PAY ITEM NAME | FROM STRUCTURE | FROM STATION | TO STRUCTURE | TO STATION | TYPE | DIAMETER (INCH) | LENGTH (FT) | TRENCH BACKFILL (CU YD) | PAY ITEM NO. |
|---|---|---|---|---|---|---|---|---|---|---|
| P 233A | STORM SEWERS, CLASS A, TYPE 2 36" | S 233A | 107+20.00 | S 233 | 107+00.00 | 2 | 36 | 25 | 17.4 | 550A0450 |
| P 233B | STORM SEWERS, CLASS A, TYPE 2 12" | S 233B | 107+50.00 | S 233A | 107+20.00 | 1 | 12 | 30 | 0.0 | 550A0340 |
| P 234 | STORM SEWERS, CLASS A, TYPE 1 12" | S 234 | 106+88.97 | S 233 | 107+00.00 | 1 | 18 | 18 | 2.4 | 550A0050 |
| P 235 | STORM SEWERS, CLASS A, TYPE 2 36" | S 235 | 109+00.00 | S 233A | 107+20.00 | 2 | 36 | 180 | 0.0 | 550A0450 |
| P 236 | STORM SEWERS, CLASS A, TYPE 2 12" | S 236 | 109+00.00 | S 235 | 109+00.00 | 2 | 12 | 7 | 0.0 | 550A0340 |
| P 237 | STORM SEWERS, CLASS A, TYPE 2 36" | S 237 | 111+00.00 | S 235 | 109+00.00 | 2 | 36 | 200 | 0.0 | 550A0450 |
| P 238 | STORM SEWERS, CLASS A, TYPE 2 12" | S 238 | 111+00.00 | S 237 | 111+00.00 | 2 | 12 | 19 | 0.0 | 550A0340 |
| P 239 | STORM SEWERS, CLASS A, TYPE 2 18" | S 239 | 107+00.00 | S 233 | 107+00.00 | 2 | 18 | 32 | 16.2 | 550A0380 |
| P 240 | STORM SEWERS, CLASS A, TYPE 2 12" | S 240 | 107+00.00 | S 244 | 107+00.00 | 2 | 12 | 27 | 13.9 | 550A0340 |
| P 241 | STORM SEWERS, CLASS A, TYPE 2 15" | S 241 | 109+00.00 | S 236 | 109+00.00 | 2 | 15 | 40 | 19.1 | 550A0360 |
| P 242 | STORM SEWERS, CLASS A, TYPE 2 12" | S 242 | 109+00.00 | S 241 | 109+00.00 | 2 | 12 | 29 | 12.6 | 550A0340 |
| P 243 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36" | S 243 | 106+95.00 | S 231A | 105+10.00 | 2 | 36 | 185 | 0.0 | 550A2600 |
| P 244 | STORM SEWERS, CLASS A, TYPE 2 12" | S 244 | 107+00.00 | S 243 | 106+95.00 | 2 | 12 | 7 | 0.0 | 550A0340 |
| P 245 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36" | S 245 | 108+65.00 | S 243 | 106+95.00 | 2 | 36 | 170 | 75.9 | 550A2600 |
| P 245A | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12" | S 245A | 108+64.75 | S 245 | 108+65.00 | 2 | 12 | 6 | 3.5 | 550A2520 |
| P 245B | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36" | S 245B | 109+50.00 | S 245 | 108+65.00 | 2 | 36 | 86 | 117.0 | 550A2600 |
| P 245C | STORM SEWERS, CLASS A, TYPE 2 12" | S 245C | 109+50.00 | S 245B | 109+50.00 | 2 | 12 | 7 | 4.2 | 550A0340 |
| P 245D | STORM SEWERS, CLASS A, TYPE 2 12" | S 245D | 109+50.00 | S 245C | 109+50.00 | 2 | 12 | 9 | 0.0 | 550A0340 |
| P 247 | STORM SEWERS, CLASS A, TYPE 2 36" | S 247 | 111+00.00 | S 245B | 109+50.00 | 2 | 36 | 150 | 243.6 | 550A0450 |
| P 247A | STORM SEWERS, CLASS A, TYPE 2 12" | S 247A | 111+00.00 | S 247 | 111+00.00 | 2 | 12 | 38 | 23.7 | 550A0340 |
| P 248 | STORM SEWERS, CLASS A, TYPE 2 12" | S 248 | 111+00.00 | S 247 | 111+00.00 | 2 | 12 | 7 | 4.2 | 550A0340 |
| P 249 | STORM SEWERS, CLASS A, TYPE 2 36" | S 249 | 113+00.00 | S 249C | 111+68.43 | 2 | 36 | 132 | 254.6 | 550A0450 |
| P 249A | STORM SEWERS, CLASS A, TYPE 1 36" | S 249A | 112+00.00 | S 249B | 111+68.43 | 1 | 36 | 33 | 0.0 | 550A0160 |
| P 249B | STORM SEWERS, CLASS A, TYPE 2 12" | S 249B | 111+68.43 | S 249C | 111+68.43 | 2 | 12 | 9 | 5.1 | 550A0340 |
| P 250 | STORM SEWERS, CLASS A, TYPE 2 12" | S 250 | 113+00.00 | S 249 | 113+00.00 | 2 | 12 | 7 | 4.8 | 550A0340 |
| P 252 | STORM SEWERS, CLASS A, TYPE 2 36" | S 252 | 113+00.00 | S 247 | 111+00.00 | 2 | 36 | 200 | 384.5 | 550A0450 |
| P 253 | STORM SEWERS, CLASS A, TYPE 2 12" | S 253 | 113+00.00 | S 252 | 113+00.00 | 2 | 12 | 7 | 4.2 | 550A0340 |

## RENWICK ROAD DRAINAGE PIPE SCHEDULE - EAST LEG

| PIPE NO. | PIPE PAY ITEM NAME | FROM STRUCTURE | FROM STATION | TO STRUCTURE | TO STATION | TYPE | DIAMETER (INCH) | LENGTH (FT) | TRENCH BACKFILL (CU YD) | PAY ITEM NO. |
|---|---|---|---|---|---|---|---|---|---|---|
| P 254 | STORM SEWERS, CLASS A, TYPE 2 12" | S 254 | 116+50.00 | S 255 | 116+50.00 | 2 | 12 | 56 | 28.1 | 550A0340 |
| P 255 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 255 | 116+50.00 | S 259 | 118+50.00 | 1 | 45x29 | 200 | 77.4 | 550A4500 |
| P 256 | STORM SEWERS, CLASS A, TYPE 2 12" | S 256 | 116+15.00 | S 257 | 116+15.00 | 2 | 12 | 42 | 19.5 | 550A0340 |
| P 257 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 257 | 116+15.00 | S 267A | 117+20.00 | 1 | 45x29 | 105 | 48.7 | 550A4500 |
| P 258 | STORM SEWERS, CLASS A, TYPE 2 12" | S 258 | 118+50.00 | S 259 | 118+50.00 | 2 | 12 | 56 | 11.9 | 550A0340 |
| P 259 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 259 | 118+50.00 | S 263 | 120+20.75 | 1 | 45x29 | 171 | 25.4 | 550A4500 |
| P 259A | STORM SEWERS, CLASS A, TYPE 2 12" | S 259A | 118+43.00 | S 259 | 118+50.00 | 2 | 12 | 9 | 2.4 | 550A0340 |
| P 260 | STORM SEWERS, CLASS A, TYPE 1 12" | S 260 | 120+30.00 | S 261 | 120+20.75 | 1 | 12 | 10 | 1.0 | 550A0050 |
| P 261 | STORM SEWERS, CLASS A, TYPE 2 15" | S 261 | 120+20.75 | S 262 | 120+20.75 | 1 | 15 | 41 | 6.3 | 550A0360 |
| P 262 | STORM SEWERS, CLASS A, TYPE 2 15" | S 262 | 120+20.75 | S 263 | 120+20.75 | 2 | 15 | 6 | 1.4 | 550A0360 |
| P 263 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 263 | 120+20.75 | S 266 | 121+50.00 | 1 | 45x29 | 129 | 38.0 | 550A4500 |
| P 264 | STORM SEWERS, CLASS A, TYPE 2 12" | S 264 | 121+50.00 | S 265 | 121+50.00 | 2 | 12 | 26 | 5.6 | 550A0340 |
| P 265 | STORM SEWERS, CLASS A, TYPE 2 12" | S 265 | 121+50.00 | S 266 | 121+50.00 | 2 | 12 | 13 | 5.7 | 550A0340 |
| P 266 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 266 | 121+50.00 | S 278 | 124+50.00 | 1 | 45x29 | 300 | 112.0 | 550A4500 |
| P 267A | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 267A | 117+20.00 | S 267 | 118+50.00 | 1 | 45x29 | 135 | 52.4 | 550A4500 |
| P 267 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36" | S 267 | 118+50.00 | S 270 | 120+20.75 | 1 | 45x29 | 170 | 53.8 | 550A4500 |
| P 268 | STORM SEWERS, CLASS A, TYPE 2 12" | S 268 | 117+19.00 | S 267A | 117+20.00 | 1 | 12 | 36 | | 550A0340 |
| P 269 | STORM SEWERS, CLASS A, TYPE 2 12" | S 269 | 118+50.00 | S 267 | 118+50.00 | 2 | 12 | 42 | 10.4 | 550A0340 |
| P 270 | STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42" | S 270 | 120+20.75 | S 274 | 121+75.00 | 1 | 53x34 | 154 | 34.5 | 550A4700 |
| P 271 | STORM SEWERS, CLASS A, TYPE 2 12" | S 271 | 120+20.75 | S 270 | 120+20.75 | 2 | 12 | 6 | 1.4 | 550A0340 |
| P 272 | STORM SEWERS, CLASS A, TYPE 1 12" | S 272 | 120+20.75 | S 271 | 120+20.75 | 1 | 12 | 38 | 6.1 | 550A0050 |

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

WILL COUNTY

RENWICK ROAD
DRAINAGE PIPE SCHEDULES

SCALE:

DRAWN BY CJO

DATE APRIL, 2011

CHECKED BY MFB

8/22/2011
P:\79766\cadd\drawings\070drSched.dgn