



F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
856	01-00170-26-TL	WILL	171	116
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO: 63570				



COMMERCIAL DRIVEWAY

NOTES:

- PREMOLDED EXPANSION JOINTS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO PCC DRIVEWAY PAVEMENT 8".
- COMBINATION CONCRETE CURB & GUTTER AND CONCRETE CURB SHALL BE MEASURED STRAIGHT ACROSS THE DRIVEWAY RETURN. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THE CURB TRANSITION SECTIONS.
- ALL POURS MUST BE SEPARATE. NO MONOLITHIC POURS WITH CURB & GUTTER, DRIVEWAY APPROACHES, AND SIDEWALKS.
- ALL SAWCUTS ARE TO BE FULL DEPTH.
- PROTECTIVE COATING SHALL BE INSTALLED ON ALL CONCRETE WORK.




RESIDENTIAL DRIVEWAY

NOTE:


ALL CONSTRUCTION TO BE DONE ACCORDING TO STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".

ALL GROUND AREAS DISTURBED SHALL BE RESEEDED AND MULCHED OR JUTE MATTED AS SOON AFTER CONSTRUCTION AS POSSIBLE.

REMOVE AND REPLACE SIDEWALK AS NECESSARY TO PROVIDE ADEQUATE TRANSITION TO EXISTING GRADES.



P.C.C. DRIVEWAY PAVEMENT, 8"



HMA DRIVEWAY PAVEMENT, 14 1/4"

DRIVEWAY CONSTRUCTION DETAILS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

CONSTRUCTION DETAILS

SCALE: NONE
DATE: APRIL, 2011

DRAWN BY: PHP
CHECKED BY: MFB