

CONSTRUCTION CODE	
STA FUNDS	
80% FED	
20% COUNTY	
ROADWAY	

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		SCH. # / SHEET #
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	28	1/4	
* 20101100	TREE TRUNK PROTECTION	EACH	7	2/4	
* 20101200	TREE ROOT PRUNING	EACH	3	3/4	
* 20200100	EARTH EXCAVATION	CU YD	4385	4/4	
* 20400800	FURNISHED EXCAVATION	CU YD	2331	5/4	
* 20800150	TRENCH BACKFILL	CU YD	117	6/5	
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1000	7/5	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11818	8/5	
* 25000210	SEEDING, CLASS 2A	ACRE	1.4	9/5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	189	10/5	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	189	11/5	
* 25100630	EROSION CONTROL BLANKET	SQ YD	6923	12/5	
* 25200110	SODDING, SALT TOLERANT	SQ YD	4896	13/5	
* 25200200	SUPPLEMENTAL WATERING	UNIT	73	14/5	
* 28000305	TEMPORARY DITCH CHECKS	FOOT	238	15/5	
* 28000400	PERIMETER EROSION BARRIER	FOOT	2274	16/5	
* 28000500	INLET AND PIPE PROTECTION	EACH	17	17/5	
* 35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	6453	18/5	
* 35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	633	19/5	
* 35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	162	20/5	
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	61	21/5	
* 40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 50	TON	738	22/5	
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3580	23/5	
* 42400800	DETECTABLE WARNINGS	SQ FT	248	24/5	
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	236	25/5	
* 44000600	SIDEWALK REMOVAL	SQ FT	10626	26/5	
* 44004250	PAVED SHOULDER REMOVAL	SQ YD	262	27/5	
* 54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	28/5	
* 54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	29/5	
* 5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	21	30/5	
* 542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	5	31/5	
* 54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	32/5	
* 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	401	33/5	
* 550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	5	34/5	
* 550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	5	35/5	
* 55100500	STORM SEWER REMOVAL 12"	FOOT	60	36/5	
* 55100700	STORM SEWER REMOVAL 15"	FOOT	10	37/5	
* 56400100	FIRE HYDRANT TO BE MOVED	EACH	6	38/5	
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	39/5	
* 60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	4	40/5	
* 60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	41/5	
* 60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	42/5	
* 60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	43/6	
* 60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	44/6	
* 60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	45/6	
* 60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	46/6	
* 60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	47/6	
* 60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	48/6	
* 60500040	REMOVING MANHOLES	EACH	1	49/6	
* 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	731	50/6	
* 60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	236	51/6	
* 67100100	MOBILIZATION	L SUM	1	N/A	
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	53/6	
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	60	54/6	
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	55/6	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	304	56/6	
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	137	57/6	
* 89501510	RELOCATE EXISTING FLASHING BEACON	EACH	1	58/6	
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	59/6	
* A2001024	TREE, ACER RUBRUM (RED MAPLE), 3" CALIPER, BALLED AND BURLAPED	EACH	1	60/6	
* K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	0.07	61/6	
* X0301508	REMOVE AND REINSTALL CONCRETE HEADWALL	EACH	1	62/6	
* X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	950	63/6	
* X6024240	INLETS, SPECIAL	EACH	1	64/6	
* X6700405	ENGINEERS FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	3	NA	
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	NA	
* X8140115	HANDHOLE TO BE ADJUSTED	EACH	1	67/6	
* Z0012450	CONCRETE STEPS	CU YD	2	68/6	
* Z0062450	SAWING PAVEMENT (FULL DEPTH)	FOOT	955	69/6	
* Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	51	70/6	

* SEE GENERAL NOTE
□ SPECIALTY ITEM
◇ SEE SPECIAL PROVISION

FILE NAME -	USER NAME - \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\$FILEL\$		DRAWN -	REVISED -					2605	09-0071-13-BT	LAKE	59	3
	PLOT SCALE - \$SCALE\$	CHECKED -	REVISED -		SCALE: NONE			SHEET NO. 1 OF 1 SHEETS			CONTRACT NO. 63619	
	PLOT DATE - \$DATE\$	DATE -	REVISED -		STA. TO STA.			ILLINOIS FED. AID PROJECT				