

43 INLETS, TYPE A, TYPE 8 GRATE				
STATION	OFFSET	LT/RT	EACH	
21+00.00	35.58	LT	1	
PAY ITEM 60236200			TOTAL	1

44 CATCH BASINS TO BE ADJUSTED				
STATION	OFFSET	LT/RT	EACH	
13+90.00	31.20	LT	1	
PAY ITEM 60250200			TOTAL	1

45 MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID				
STATION	OFFSET	LT/RT	EACH	
12+02.77	42.57	LT	1	
14+47.05	43.39	LT	1	
21+75	43.25	LT	1	
PAY ITEM 60258800			TOTAL	3

46 MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID				
STATION	OFFSET	LT/RT	EACH	
0+82.56	42.44	LT	1	
71+21.20	34.06	LT	1	
PAY ITEM 60258200			TOTAL	2

47 VALVE VAULTS TO BE ADJUSTED WITH TYPE 1 FRAME, CLOSED LID				
STATION	OFFSET	LT/RT	EACH	
4+98.23	43.67	LT	1	
8+52.50	49.26	LT	1	
75+20.06	41.53	LT	1	
PAY ITEM 60265900			TOTAL	3

48 VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID				
STATION	OFFSET	LT/RT	EACH	
78+24.64	34.10	LT	1	
PAY ITEM 60266300			TOTAL	1

49 REMOVING MANHOLES				
STATION	OFFSET	LT/RT	EACH	
22+77.40	42.70	LT	1	
PAY ITEM 60500040			TOTAL	1

50 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				
FROM STATION	TO STATION	LT/RT	LENGTH (FT)	
71+42.02	78+72.53	LT	730.51	
PAY ITEM 60605000			TOTAL	731

51 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)				
FROM STATION	TO STATION	LT/RT	LENGTH (FT)	
MIDLOTHIAN ROAD				
0+54.19	0+61.37	LT	18.77	
3+98.37	4+04.50	LT	15.31	
4+29.73	4+43.07	LT	20.02	
7+65.04	7+81.83	LT	22.95	
8+23.04	8+35.05	LT	21.09	
12+50.23	12+55.58	LT	16.16	
13+29.95	13+34.95	LT	16.02	
16+75.76	17+00.57	LT	31.86	
17+42.35	17+60.76	LT	28.14	
25+93.43	26+00.83	LT	15.77	
112+15.73	112+23.87	LT	15.13	
SHEFIELD AVENUE				
300+46.72	300+59.30	RT	14.80	
PAY ITEM 60605100			TOTAL	236

53 REMOVE SIGN PANEL ASSEMBLY - TYPE A				
STATION	OFFSET	LT/RT	EACH	
5+98		LT	1	
78+65		LT	1	
96+14		LT	1	
PAY ITEM 72400100			TOTAL	3

54 REMOVE SIGN PANEL - TYPE 1				
STATION	LT/RT	SQ FT		
5+22	LT	7.5		
9+11	LT	7.5		
14+70	LT	5		
18+38	LT	7.5		
20+63	LT	5		
25+95	LT	5.5		
78+65	LT	4		
78+65	LT	4		
96+14	LT	4		
96+14	LT	4		
303+29	RT	6		
PAY ITEM 72400310			TOTAL	60

55 RELOCATE SIGN PANEL ASSEMBLY - TYPE A				
STATION	OFFSET	LT/RT	EACH	
301+25		RT	1	
PAY ITEM 72400500			TOTAL	1

56 THERMOPLASTIC PAVEMENT MARKING - LINE 12"				
FROM STATION	TO STATION	OFFSET	LT/RT	LENGTH (FEET)
16+95	17+49	41.50	LT	152
300+50	300+58	50.00	LT	152
PAY ITEM 78000600			TOTAL	304

57 PAVEMENT MARKING REMOVAL				
FROM STATION	TO STATION	LT/RT	AREA (SQ FT)	
16+94.87	17+46.96	LT	26	
16+99.26	17+43.81	LT	23	
26+00.85	26+28.48	LT	88	
PAY ITEM 78300100			TOTAL	137

58 RELOCATE EXISTING FLASHING BEACON				
STATION	OFFSET	LT/RT	EACH	
16+60	43.50	LT	1	
PAY ITEM 89501510			TOTAL	1

59 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT				
STATION	OFFSET	LT/RT	EACH	
21+82		LT	1	
PAY ITEM 89502375			TOTAL	1

60 TREE, ACER RUBRUM (RED MAPLE), 3" CALIPER, BALLED AND BURLAPED				
STATION	OFFSET	LT/RT	EACH	
65+66.49	124.33	LT	1	
PAY ITEM A2001024			TOTAL	1

61 PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT				
STATION	OFFSET	LT/RT	EACH	
3+37.58	56.43	LT	1	
3+42.33	55.71	LT	1	
3+46.92	55.57	LT	1	
3+52.31	55.69	LT	1	
3+57.63	55.95	LT	1	
3+62.20	56.31	LT	1	
3+66.30	56.46	LT	1	
PAY ITEM K0012990			TOTAL	0.07 UNITS

62 REMOVE AND REINSTALL CONCRETE HEADWALL				
STATION	OFFSET	LT/RT	EACH	
105+47.43	43.33	LT	1	
PAY ITEM X0301508			TOTAL	1

63 PIPE UNDERDRAINS 4" (MODIFIED)				
FROM STATION	TO STATION	LT/RT	LENGTH (FEET)	
13+90	16+00	LT	210	
71+50	73+00	LT	150	
73+00	74+50	LT	150	
74+50	77+00	LT	250	
77+00	78+72.50	LT	173	
105+45		LT	17	
PAY ITEM X6013900			TOTAL	950

64 INLETS, SPECIAL				
STATION	OFFSET	LT/RT	EACH	
22+78.08	46.90	LT	1	
PAY ITEM X6024240			TOTAL	1

67 HANDHOLE TO BE ADJUSTED				
STATION	OFFSET	LT/RT	EACH	
0+69.04	46.88	LT	1	
PAY ITEM X8140115			TOTAL	1

68 CONCRETE STEPS				
STATION	OFFSET	LT/RT	VOLUME (CU YD)	
4+55.47		LT	2	
PAY ITEM Z0012450			TOTAL	2

69 SAWING PAVEMENT (FULL DEPTH)				
FROM STATION	TO STATION	LT/RT	LENGTH (FOOT)	
MIDLOTHIAN ROAD				
6+41.50	6+53.66	LT	13	
13+67.98	13+77.90	LT	10	
16+90.44	16+94.35	LT	4	
17+48.11	17+52.12	LT	4	
25+76.33	25+82.44	LT	7	
64+42.19	65+00.19	LT	66	
65+93.58	66+22.67	LT	34	
70+09.21	70+65.02	LT	57	
71+42.02	78+72.53	LT	731	
78+90.00	78+90.00	LT	9	
95+90.00	95+90.00	LT	8	
SHEFIELD AVENUE				
303+29.48	303+37.45	RT	8	
303+50.76	303+50.76	RT	4	
PAY ITEM Z0062450			TOTAL	955

70 GEOTECHNICAL REINFORCEMENT				
FROM STATION	TO STATION	LT/RT	AREA (SQ YD)	
75+43	75+63	LT	51.00	
PAY ITEM Z0028415			TOTAL	51