



MIDLOTHIAN ROAD CENTERLINE COORDINATES			
DESCRIPTION	STATION	NORTHING	EASTING
PC	0+00.00	554.23	990.46
PT	3+99.98	954.08	981.95
POT	33+13.68	3867.78	970.91
POT	52+96.12	5849.50	964.02
PC	63+06.21	6859.58	960.15
PT	73+06.21	7859.56	953.82
POT	113+05.33	11858.52	918.51

CONTROL POINTS						
NUMBER	DESCRIPTION	STATION	OFFSET	NORTHING	EASTING	ELEVATION
CP1	MAG NAIL	4+45.81	18.23 RIGHT	1000.00	1000.00	779.56
CP2	MAG NAIL	8+20.75	60.38 LEFT	1374.64	919.98	782.86
CP3	MAG NAIL	17+49.18	44.75 LEFT	2303.12	932.08	784.03
CP4	MAG NAIL	26+86.03	5.89 LEFT	3240.11	967.40	786.88
CP5	MAG NAIL	54+16.51	36.95 LEFT	5969.74	926.61	803.89
CP6	IRON ROD	63+69.15	59.14 LEFT	6922.27	900.75	801.60
CP7	SPIKE	66+55.13	16.32 RIGHT	7208.59	974.82	794.59
CP8	MAG NAIL	66+85.84	114.20 LEFT	7238.55	844.13	805.51
CP9	MAG NAIL	68+45.08	22.58 RIGHT	7398.59	979.94	796.54
CP10	MAG NAIL	71+27.31	113.88 LEFT	7679.76	841.44	805.70
CP11	MAG NAIL	72+86.87	16.42 RIGHT	7840.37	970.40	807.83
CP12	MAG NAIL	83+14.92	33.51 LEFT	8867.93	911.40	812.98
CP13	SPIKE	97+11.29	23.20 RIGHT	10264.75	955.78	810.59
CP14	SPIKE	106+45.93	21.94 RIGHT	11199.34	946.27	821.38
CP15	MAG NAIL	113+04.77	47.89 LEFT	11857.54	870.62	820.64

BENCHMARKS						
NUMBER	DESCRIPTION	STATION	OFFSET	NORTHING	EASTING	ELEVATION
BM1	BRASS MONUMENT	59+55.75	6.34 RIGHT	6509.14	967.83	804.00
BM2	BRASS MONUMENT	86+01.97	15.81 RIGHT	9155.41	958.18	809.19

FILE NAME	USER NAME - #USERS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MIDLOTHIAN ROAD HORIZONTAL ALIGNMENT SHEET		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILES		DRAWN -	REVISED -		SCALE: 1" = 200'	SHEET NO. 1 OF 2 SHEETS	STA. 0+00.00 TO STA. 113+05.33	2605	09-00171-13-BT	LAKE	59	8
		PLOT SCALE - #SCALE\$	REVISED -					CONTRACT NO. 63619				
		PLOT DATE - #DATE\$	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				