

# SCHEDULE OF QUANTITIES

## 20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
8	88+12.19	24.0		8"
7	88+13.89	29.6		7"
6	88+27.94	30.3		6"
12	99+09.90	63.7		12"
12	91+10.10	44.2		MS 6", 6"
6	91+16.60	45.1		6"
14	91+48.60	44.4		14"
12	91+51.20	43.9		12"
10	91+94.23	49.0		10"
12	91+99.10	59.3		12.0
12	92+01.10	57.8		12"
16	92+52.35	29.1		MS-8", 8"
12	92+58.87		28.4	MS-6", 6"
10	93+89.93		41.0	10"
<b>149</b>	<b>TOTAL</b>			

## 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
18	94+09.64		39.93	18"
40	94+68.67		41.68	36"
36	95+74.97	30.52		36"
<b>94</b>	<b>TOTAL</b>			

## 20101100 TREE TRUNK PROTECTION

EACH	LOCATION	O/S (LT.)		REMARKS
1	88+42.80	32.1	RT	
1	89+14.60	33.0	RT	
1	91+46.80	71.4	LT	
1	93+21.20	41.3	RT	
1	94+41.40	33.1	LT	
1	94+68.70	41.7		
1	95+04.50	33.9	LT	
<b>7</b>	<b>TOTAL</b>			

## 20800150 TRENCH BACKFILL

VOLUME (CU YD)	LOCATION	O/S	LENGTH (FT)	WIDTH (FT)	DEPTH (FT)	REMARKS
105.4	90+88.10	RT	87.6	5.0	6.5	18" STORM
26.4	94+23.70	RT	24.6	5.0	5.8	18" STORM
12.7	95+58.90	RT	19.9	4.0	4.3	15" STORM
<b>145.0</b>						

## 50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION		O/S	REMARKS
56	90+58.50	091+14.50	LT	DRIVEWAY
171	90+59.00	092+30.29	LT	DRAIN TILE
27	95+46.00	095+73.00	RT	DRIVEWAY
<b>255</b>	<b>TOTAL</b>			

## 54215418 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 18"

EACH	LOCATION	O/S		REMARKS
1	92+26.40	25.0	RT	
1	92+72.60	25.0	RT	
<b>2</b>	<b>TOTAL</b>			

## 54215550 METAL END SECTIONS 15"

EACH	LOCATION	O/S		REMARKS
1	92+32.70	65.0	LT	
<b>1</b>	<b>TOTAL</b>			

## 550A0070 STORM SEWERS, CLASS A, TYPE 1 15"

FOOT	LOCATION		O/S	REMARKS
5	94+96.90	94+96.90	RT	
79	94+96.90	95+76.30	RT	
24	92+09.60	92+32.70	LT	
<b>108</b>	<b>TOTAL</b>			

FILE NAME = P:\CUBBEL WEST Projects\220910\0073 Hoopa\IT\Civil\Draw\Sht\Schedule.dgn