



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = P:\CBBEL\WEST Projects\2209\95-0073\Hospa\IT\Cvt\1\Sign\Sign\TOT_01-TC22.dgn

FILE NAME = P:\CBBEL\WEST Projects\2209\95-0073\Hospa\IT\Cvt\1\Sign\Sign\TOT_01-TC22.dgn	USER NAME = gaglionobt	DESIGNED -	REVISED - R. MIRS 09-15-97	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		ARTERIAL ROAD INFORMATION SIGN		T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED - R. MIRS 12-11-97					2442	04-08107-00-BR	KANE	80	62	
		PLOT SCALE = 50.000' / IN.	REVISED - T. RAMMACHER 02-02-99					TC-22				CONTRACT NO. 63644	
		PLOT DATE = 12/16/2011	REVISED - C. JUCIUS 01-31-07					SCALE: NONE		SHEET NO. 62 OF 80 SHEETS		STA. TO STA.	