

DATE	
BY	
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS CHECKED	
NO.	

DATE	
BY	
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS CHECKED	
NO.	

EXTENDED SCHEDULE OF EARTH QUANTITIES										
STATION	DISTANCE	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION
(XX+XX)	(FT)	(SQ FT)	(SQ FT)	(SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	(CU FT)	(CU FT)	(CU FT)
199+50	50	7	22	1	4	22	2	200	1,075	100
200+00	50	0	14	5	4	18	3	175	900	150
200+50	50	0	21	19	0	18	12	0	875	600
201+00	50	0	39	79	0	30	49	0	1,500	2,450
201+50	50	0	57	166	0	48	123	0	2,400	6,125
202+00	50	0	57	164	0	57	165	0	2,850	8,250
202+50	50	0	45	101	0	51	133	0	2,550	6,625
203+00	50	0	27	36	0	36	69	0	1,800	3,425
203+50	50	0	20	18	0	24	27	0	1,175	1,350
204+00	50	0	10	3	0	15	11	0	750	525
204+50	50	7	16	1	4	13	2	175	650	100
205+00	50	15	19	1	11	18	1	550	875	50
205+50	50	25	23	1	20	21	1	1,000	1,050	50
206+00	50	16	24	1	21	24	1	1,025	1,175	50
206+50	50	23	25	1	20	25	1	975	1,225	50
207+00	50	18	27	1	21	26	1	1,025	1,300	50
207+50	50	5	17	3	12	22	2	575	1,100	100
208+00	50	0	0	0	3	9	2	125	425	75
208+50	50	0	0	0	0	0	0	0	0	0
SUBTOTAL GRAND AVENUE STAGE 1								16,650	38,200	31,150
GRAND AVENUE STAGE 2										
192+50	50	0	0	0	4	0	3	175	0	125
193+00	50	7	0	5	7	0	5	325	0	250
193+50	50	6	0	5	6	0	21	275	0	1,025
194+00	50	5	0	36	5	0	40	250	0	1,975
194+50	50	5	0	43	5	0	44	250	0	2,200
195+00	50	5	0	45	5	0	41	250	0	2,025
195+50	50	5	0	36	5	0	37	250	0	1,850
196+00	50	5	0	38	5	0	37	250	0	1,825
196+50	50	5	0	35	5	0	44	250	0	2,175
197+00	50	5	0	52	6	2	41	275	75	2,025
197+50	50	6	3	29	6	15	49	300	750	2,450
198+00	50	6	27	69						

EXTENDED SCHEDULE OF EARTH QUANTITIES										
STATION	DISTANCE	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION	TOPSOIL EXCAVATION AND PLACEMENT	FURNISHED EXCAVATION
(XX+XX)	(FT)	(SQ FT)	(SQ FT)	(SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	AVG. (SQ FT)	(CU FT)	(CU FT)	(CU FT)
198+50	50	5	26	67	6	27	68	275	1,325	3,400
199+00	50	6	5	16	6	16	42	275	775	2,075
199+50	50	5	0	20	6	3	18	275	125	900
200+00	50	5	0	9	5	0	15	250	0	725
200+50	50	5	0	9	5	0	9	250	0	450
201+00	50	5	0	9	5	0	9	250	0	450
201+50	50	5	0	8	5	0	9	250	0	425
202+00	50	5	0	8	5	0	8	250	0	400
202+50	50	5	0	8	5	0	8	250	0	400
203+00	50	5	0	8	5	0	8	250	0	400
203+50	50	5	0	7	5	0	8	250	0	375
204+00	50	5	0	6	5	0	7	250	0	325
204+50	50	5	0	14	5	0	10	250	0	500
205+00	50	5	0	23	5	0	19	250	0	925
205+50	50	5	0	28	5	0	26	250	0	1,275
206+00	50	5	0	33	5	0	31	250	0	1,525
206+50	50	5	0	34	5	0	34	250	0	1,675
207+00	50	6	0	34	6	0	34	275	0	1,700
207+50	50	1	0	11	4	0	23	175	0	1,125
208+00	50	2	0	0	2	0	6	75	0	275
SUBTOTAL GRAND AVENUE STAGE 2								7,700	3,050	37,250

NOTE:
REFER TO THE CONDENSED SCHEDULE OF EARTH QUANTITIES FOR PROJECT TOTALS.