


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				HBP/TBP FUNDS		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
				ROADWAY	BRIDGE	TRAINEES
				0004	0011	0042
				URBAN	URBAN	URBAN
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	625	625		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	165	165		
40600300	AGGREGATE (PRIME COAT)	TON	3.22	3.22		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160		
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	1,615	1,615		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	535	535		
44000100	PAVEMENT REMOVAL	SQ YD	2,560	2,560		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	392	392		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	505	505		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	94	94		
50200100	STRUCTURE EXCAVATION	CU YD	99		99	
50200300	COFFERDAM EXCAVATION	CU YD	43		43	
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1	
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1	
50300225	CONCRETE STRUCTURES	CU YD	72		72	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	107		107	
50300260	BRIDGE DECK GROOVING	SQ YD	583		583	
50300280	CONCRETE ENCASEMENT	CU YD	21		21	
50300300	PROTECTIVE COAT	SQ YD	683		683	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	3,981		3,981	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	42,260		42,260	
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	196		196	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	425		425	
51202305	DRIVING PILES	FOOT	621		621	
51203200	TEST PILE METAL SHELLS	EACH	1		1	

▲ SPECIALTY ITEMS

FILE NAME = S:\JUL\6800-6899\6842\007\Micros\CADD Sheets\DI-63666-ah-500.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennisw
DESIGNED VLF
DRAWN B/JF
CHECKED AJS
PLOT DATE = 1/9/2013

REVISED
REVISED
REVISED
REVISED

**MCHENRY COUNTY DIVISION OF TRANSPORTATION
HILL ROAD BRIDGE OVER
NORTH BRANCH NIPPERSINK CREEK**

SUMMARY OF QUANTITIES
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
21	08-00356-00-BR	MCHENRY	67	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63666	