


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				HBP/TBP FUNDS		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
				ROADWAY	BRIDGE	TRAINEES
				0004	0011	0042
				URBAN	URBAN	URBAN
51203800	TEST PILE STEEL HP14X73	EACH	3		3	
51204650	PILE SHOES	EACH	20		20	
51500100	NAME PLATES	EACH	1		1	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2		
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	2	2		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	56	56		
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	40	40		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	11	11		
58700300	CONCRETE SEALER	SQ FT	845		845	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	54		54	
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24	FOOT	20	20		
△	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	250	250	
△	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	
△	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
	63200310	GUARDRAIL REMOVAL	FOOT	58	58	
	66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	11	11	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
	67100100	MOBILIZATION	L SUM	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	
△	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,460	3,460	
△	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	685	685	
△	78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
△	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
△	A2002912	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	4	

△ SPECIALTY ITEMS

FILE NAME = S:\JOLI 6602-6895\6842\007\Micros\CADD Sheets\DI-63666-ah-500.dgn



1170 SOUTH HOBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennisw
DESIGNED VLF
DRAWN B/JF
CHECKED AJS
DATE

REVISED -
REVISED -
REVISED -
REVISED -

**MCHENRY COUNTY DIVISION OF TRANSPORTATION
HILL ROAD BRIDGE OVER
NORTH BRANCH NIPPERSINK CREEK**

SUMMARY OF QUANTITIES
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
21	08-00356-00-BR	MCHENRY	67	6
CONTRACT NO. 63666			ILLINOIS FED. AID PROJECT	