


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				HBP/TBP FUNDS		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
				ROADWAY	BRIDGE	TRAINEES
				0004	0011	0042
				URBAN	URBAN	URBAN
▲ A2006512	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8	8		
▲ A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	2	2		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	96		96	
X2800300	TEMPORARY DITCH CHECKS (SPECIAL)	EACH	13	13		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1		
▲ X6310088	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	EACH	4	4		
▲ X7810300	RECESSED REFLECTIVE PAVMENT MARKER	EACH	10	10		
XX008438	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		
XX008458	CONCRETE WEARING SURFACE, (VARIABLE DEPTH)	CU YD	88		88	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	1,615	1,615		
▲ Z0007124	STEEL RAILING (SPECIAL)	FOOT	282		282	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	530	530		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	26	26		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50	50		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130		130	
Z0066400	STABILIZED DRIVEWAYS 6"	SQ YD	81	81		
Z0076600	TRAINEES	HOUR	500			500

▲ SPECIALTY ITEMS

FILE NAME = S:\JUL 6500--6895\6842\027\Micros\CADD Sheets\DJ-63666-ah-500.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200

USER NAME = dennisw  
DESIGNED VLF  
DRAWN BJF  
CHECKED AJS  
PLOT DATE = 1/9/2012

REVISED -  
REVISED -  
REVISED -  
REVISED -

**MCHENRY COUNTY DIVISION OF TRANSPORTATION  
HILL ROAD BRIDGE OVER  
NORTH BRANCH NIPPERSINK CREEK**

**SUMMARY OF QUANTITIES**  
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
21	08-00356-00-BR	MCHENRY	67	7
CONTRACT NO. 63666			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	