


**RESTORATION OF WORK AREA.**  
 RESTORATION OF ANY PREVIOUSLY COMPLETED PAY ITEMS IN THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE COST OF THE RELATED PAY ITEM BEING PLACED SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO PREVIOUSLY SODDED AREAS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS OR PREVIOUSLY SEEDED AREAS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE MANUFACTURED BY THE ECONOLITE CORPORATION TO MATCH THE EXISTING VILLAGE MAINTAINED SYSTEM



FILE NAME =	USER NAME = #USER#	DESIGNED - JAS	REVISED -
P:\070116\oad\phase 2\dwg\070116-shl-ta.dgn		DRAWN - JH	REVISED -
PLOT SCALE = #SCALE#		CHECKED - CM	REVISED -
PLOT DATE = 1/5/2012		DATE - AUGUST 2009	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**



**TRAFFIC SIGNAL PLAN  
 PLAINFIELD NAPERVILLE RD AT 119TH ST / RODEO DR**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	04-00036-22-TL	WILL	152	57
<b>CONTRACT NO. 63671</b>				

SCALE: 1" = 20' SHEET NO. 1 OF 2 SHEETS STA. TO STA.

ILLINOIS FED. AID PROJECT