


RESTORATION OF WORK AREA.
 RESTORATION OF ANY PREVIOUSLY COMPLETED PAY ITEMS IN THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE COST OF THE RELATED PAY ITEM BEING PLACED SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO PREVIOUSLY SODDED AREAS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS OR PREVIOUSLY SEEDED AREAS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.



FILE NAME = F:\070116\cod\phase 2\dwg\070116-sht-ts.dgn	USER NAME = #USER#	DESIGNED - JAS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HLR	TRAFFIC SIGNAL PLAN PLAINFIELD NAPERVILLE RD AT 119TH ST / RODEO DR	F.A.J. RTE. 324	SECTION 04-00036-22-TL	COUNTY WILL	TOTAL SHEETS 152	SHEET NO. 58			
PLOT SCALE = #SCALE#	CHECKED - CM	DATE - FEBRUARY 2009	REVISED -				SCALE: 1" = 20'		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.		CONTRACT NO. 63671	
PLOT DATE = 1/5/2012	DATE - FEBRUARY 2009	REVISED -	ILLINOIS FED. AID PROJECT											