

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL	80% FEDERAL		80% FED. / 20% STATE		
					20% STATE	20% STATE				
					0001	0008	0008	0008	0008	0008
					ROADWAY	US RTE 20 OVER PECATONICA RIVER S.N. 089-0082	US RTE 20 OVER JANE ADDAMS TRAIL S.N. 089-0083	SLOPE WALL AT HARLEM CTR. RD. SN 089-0044	US 20 OVER PECATONKA RIVER SN 089-0045	US 20 OVER JANE ADDAMS TRAIL SN 089-0055
	40600895	CONSTRUCTING TEST STRIP	EACH	3	3					
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9,970	9,970					
	40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	43,393	43,393					
	40702700	FURNISH PROFILOGRAPH	L SUM	1	1					
	42001200	PAVEMENT FABRIC	SQ YD	275	275					
	42001500	PORTLAND CEMENT CONCRETE BRIDGE APPROACH	SQ YD	92					39	53
	44000100	PAVEMENT REMOVAL <i>SHOULDER PAVEMENT</i>	SQ YD	2,020	2,020					
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	36,181	36,181					
	44000300	CURB REMOVAL	FOOT	475	475					
	44004250	PAVED SHOULDER REMOVAL	SQ YD	2,902	2,902					
	44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	83	83					
	44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	60	60					
	44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	1,870	1,870					
	44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	248	248					
	44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	68	68					
	44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	207	207					
	44201299	DOWEL BARS 1 1/2"	EACH	760	760					
	44213000	PATCHING REINFORCEMENT	SQ YD	2,012	2,012					
	44213200	SAW CUTS	FOOT	4,226	4,226					
	44213204	TIE BARS 3/4"	EACH	737	737					
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	35,052	35,052					
	50104650	SLOPE WALL REMOVAL	SQ YD	315					315	
	50300225	CONCRETE STRUCTURES	CU YD	55.3			29.1	26.2		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	258.4			125.6	132.8		
	50300260	BRIDGE DECK GROOVING	SQ YD	514			257	257		
	50300300	PROTECTIVE COAT	SQ YD	577			276	301		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	68,620	2,010		32,730	33,880		
	51100100	SLOPE WALL 4 INCH	SQ YD	280					280	
	542A0229	PIPE CULVERTS, CLASS A, TYPE I, 24"	FOOT	130	130					

△ NON-PARTICIPATING ITEM (100% STATE)  
• SPECIALTY ITEM

**PARSONS BRINCKERHOFF**  
280 West Monroe St., Suite 900  
Chicago, IL 60606, (312) 782-6160

USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 50.00' / IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 6
FINAL SUBMITTAL			CONTRACT NO. 64860	
[ILLINOIS] FED. AID PROJECT P-92-014-03				

Rev. 2-22-12

T:\580144\Civil\PAV\_Plans\28P\AV500206.dgn