

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 CONT.

40603310		HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50					TON		9,970	
STATION	WIDTH	TO	STATION	WIDTH	DEPTH	LT/RT	DENSITY	DESCRIPTION	QUANTITY	
	FT			FT	IN		LB/SY*IN		TON	
568+16.08	8.0		568+87.85	6	2	LT	112	WB INSIDE SHOULDER	6.3	
570+92.17	6.0		571+34.00	6	2	LT	112	WB INSIDE SHOULDER	3.1	
571+34.00	6.0		571+94.00	8	2	LT	112	WB INSIDE SHOULDER	5.2	
571+94.00	8.0		640+00.00	8	2	LT	112	WB INSIDE SHOULDER	677.6	
629+00.00	10.0		633+93.41	10	2	LT	112	EB INSIDE SHOULDER	61.4	
HOT-MIX ASPHALT SURFACE COURSE BEHIND GUARDRAIL										
504+61.34	3.0		508+78.84	3	2	LT	112	WB OUTSIDE GUARDRAIL	15.6	
508+78.84	3.0		509+03.84	10	2	LT	112	WB OUTSIDE GUARDRAIL	2.0	
509+03.84	10.0		509+28.84	10	2	LT	112	WB OUTSIDE GUARDRAIL	3.1	
509+28.84	10.0		509+51.34	0	2	LT	112	WB OUTSIDE GUARDRAIL	1.4	
536+30.43	3.0		536+57.59	3	2	LT	112	WB OUTSIDE GR TERM. AT BRIDGE	1.0	
544+38.73	3.0		568+96.68	3	2	LT	112	WB OUTSIDE GUARDRAIL	91.8	
570+71.18	3.0		577+89.93	3	2	LT	112	WB OUTSIDE GUARDRAIL	26.8	
577+89.93	3.0		578+14.93	10	2	LT	112	WB OUTSIDE GUARDRAIL	2.0	
578+14.93	10.0		578+39.93	10	2	LT	112	WB OUTSIDE GUARDRAIL	3.1	
578+39.93	10.0		578+62.43	0	2	LT	112	WB OUTSIDE GUARDRAIL	1.4	
536+51.59	3.0		536+78.76	3	2	LT	112	WB INSIDE GR TERM. AT BRIDGE	1.0	
544+61.25	3.0		548+36.23	3	2	LT	112	WB INSIDE GUARDRAIL	14.0	
548+36.23	3.0		548+61.15	10	2	LT	112	WB INSIDE GUARDRAIL	2.0	
548+61.15	10.0		548+86.15	10	2	LT	112	WB INSIDE GUARDRAIL	3.1	
548+86.15	10.0		549+08.73	0	2	LT	112	WB INSIDE GUARDRAIL	1.4	
568+76.08	3.0		569+03.25	3	2	LT	112	WB INSIDE GR TERM. AT BRIDGE	1.0	
570+77.75	3.0		574+59.05	3	2	LT	112	WB INSIDE GUARDRAIL	14.2	
574+59.05	3.0		574+84.05	10	2	LT	112	WB INSIDE GUARDRAIL	2.0	
574+84.05	10.0		575+09.05	10	2	LT	112	WB INSIDE GUARDRAIL	3.1	
575+09.05	10.0		575+31.54	0	2	LT	112	WB INSIDE GUARDRAIL	1.4	
MILL OUT 3" & OVERLAY 3" EXISTING SHOULDERS WITHIN PROJECT LIMITS										
471+38.61	10.0		536+93.64	10.0	3	RT	112	EB INSIDE SHOULDER	1,223.6	
544+72.34	10.0		569+15.41	10.0	3	RT	112	EB INSIDE SHOULDER	456.0	
570+80.85	10.0		629+00.00	10.0	3	RT	112	EB INSIDE SHOULDER	1,086.2	
633+93.41	10.0		640+00.00	10.0	3	RT	112	EB INSIDE SHOULDER	113.2	
463+36.08	10.0		537+15.69	10.0	3	RT	112	EB OUTSIDE SHOULDER	1,377.5	
544+84.78	10.0		569+29.15	10.0	3	RT	112	EB OUTSIDE SHOULDER	456.3	
570+85.00	10.0		640+00.00	10.0	3	RT	112	EB OUTSIDE SHOULDER	1,290.8	
640+00.00	8.0		644+00.00	8.0	3	RT	112	WB INSIDE SHOULDER	59.7	
EXISTING WB SHOULDER, 500 SQ YD									56.0	
TOTAL									9,970	

40701956		HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"					SQ YD		43,393	
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY			
	FT			FT			SQ YD			
66+07.36	10.0		69+00.00	21.3	CT	TRAVEL LANES	509			
69+00.00	11.3		71+32.83	36.7	CT	TRAVEL LANES	621			
71+32.83	19.3		72+63.90	24.0	RT	TRAVEL LANES	315			
72+63.90	24.0		77+00.00	24.0	CT	TRAVEL LANES	1,163			
477+00.00	24.0		536+57.58	24.0	CT	TRAVEL LANES	15,887			
544+61.99	24.0		568+86.87	24.0	CT	TRAVEL LANES	6,466			
570+88.23	24.0		640+00.00	24.0	CT	TRAVEL LANES	18,431			
TOTAL									43,393	


44000100		PAVEMENT REMOVAL					SQ YD		2,020	
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY			
	FT			FT			SQ YD			
629+00.00	0.0		632+40.79	18.5	CT	XO TRAVEL LANE	350			
632+40.79	16.3		636+26.35	19.5	CT	XO TRAVEL LANE	767			
636+26.35	19.5		640+00.00	24.0	CT	XO TRAVEL LANE	903			
TOTAL									2,020	

44000161		HOT-MIX ASPHALT SURFACE REMOVAL, 3"					SQ YD		36,181	
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY			
	FT			FT			SQ YD			
471+38.60	10.0		536+93.64	10.0	RT	EB INSIDE SHOULDER	7,283			
544+72.34	10.0		569+15.11	10.0	RT	EB INSIDE SHOULDER	2,714			
570+80.85	10.0		629+00.00	10.0	RT	EB INSIDE SHOULDER	6,466			
633+93.41	10.0		640+00.00	10.0	RT	EB INSIDE SHOULDER	674			
463+36.08	10.0		537+15.63	10.0	RT	EB OUTSIDE SHOULDER	8,199			
544+84.78	10.0		569+29.15	10.0	RT	EB OUTSIDE SHOULDER	2,716			
570+85.00	10.0		640+00.00	10.0	RT	EB OUTSIDE SHOULDER	7,683			
640+00.00	10.0		644+00.00	10.0	LT	WB INSIDE SHOULDER	444			
TOTAL									36,181	

44004250		PAVED SHOULDER REMOVAL					SQ YD		2,902	
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY			
	FT			FT			SQ YD			
466+11.08	10.0		471+38.60	10.0	LT	EB INSIDE	586			
629+00.00	10.0		640+00.00	10.0	LT	XO OUTSIDE	1,247			
632+40.79	2.0		633+93.41	15.9	RT	XO INSIDE	152			
633+93.41	6.0		640+00.00	6.0	RT	XO INSIDE	418			
EXISTING WB SHOULDER, 500 SQ YD									500	
TOTAL									2,902	

44000300		CURB REMOVAL					FOOT		475	
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY			
	FT			FT			FOOT			
570+52.58	10.0		575+27.58	10.0	LT	EB INSIDE	475			
TOTAL									475	

T:\18844\A\Civil\PAV.Plans\28PAV\SCHED05.dgn



USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/26/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 16 SHEETS STA. TO STA.

F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 19
FINAL SUBMITTAL			CONTRACT NO. 64860	
[ILLINOIS] FED. AID PROJECT P-92-014-03				

Rev. 2-22-12