CLASS A PATCHES

12 FEET LANE WIDTH

STATION	LENGTH OF PATCH		LENGTH OF PATCH		AREA OF PATCHES						SAW CUTS	TIE BARS 3/4"	PATCHING REINFORCEMT
					TYPE 2		TYPE 3		TYPE 4				
	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	(4W+ ?L)		
	FEET	FEET	FEET	FEET	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FEET	EACH	SQ YD
					44200541		44200545		44200547		44213200	44213204	44213000
472+80.00	170		170						226.7		218	84	226.7
474+44.00	370		370						493.3		418	184	493.3
479+87.00	50		50						66.7		98	24	66.7
487+26.00	121		121						161.3		169	60	161.3
488+12.00		70		70						93.3	118	34	93.3
491+76.00		123		123						164.0	171	61	164.0
525+01.00	6		6		8.0						54	0	8.0
532+68.00	6		6		8.0						54	0	8.0
533+84.00		15		15				20.0			63		20.0
537+06.00	8	15	8	15	10.7			20.0			111		30.7
547+30.00	6	15	6	15	8.0			20.0			111		28.0
558+81.00	20		20						26.7		68	9	26.7
561+38.00	62		62						82.7		110	30	82.7
563+48.00	136		136						181.3		184	67	181.3
566+10.00	90		90						120.0		138	44	120.0
568+54.00	8	8	8	8	10.7	10.7					104		21.3
572+05.00	10	10	10	10	13.3	13.3					106		26.7
597+82.00	55	110	55	110					73.3	146.7	206	54	220.0
625+65.00		25		25						33.3	73	12	33.3
				TOTAL	83		60.0		1870		2574	663	2012

CLASS B PATCHES

12 FEET LANE WIDTH

STATION	LENGTH OF PATCH		TYPE 2		TYPE 3		TYPE 4		SAW CUTS	DOWEL BARS 1 1/2"	TIE BARS	PAVEMENT FABRIC
	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	(3W+ ?L)			
	FEET	FEET	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FEET	EACH	EACH	SQ YD
			44200982		44200986		44200988		44213200	44201299	44213204	42001200
626+12.00		20						26.7	56	20	9	26.7
627+07.00	15	6		8	20.0				87	40	0	20.0
627+37.00	15	18	8			24.0			90	40		24.0
627+88.00	15	6		8			26.7		92	40	9	26.7
630+24.00	15	50	8					66.7	122	40	24	66.7
630+65.00	15	18	8			24.0			90	40		24.0
631+82.00	15	6		8			86.7		137	40	32	86.7
Pavement Patching, Class B at East End of project (Existing 4 lane section) EASTBOUND												
633+52.00		6		8					42	20		
633+56.00	6	6	8	8					78	40		
636+00.00	6	6	8	8					78	40		
636+49.00	6	6	8	8					78	40		
638+40.00	6	6	8	8					78	40		
638+89.00	6	6	8	8					78	40		
639+28.00	6	6	8	8					78	40		
639+65.00	6	6	8	8					78	40		
640+08.00	6	6	8	8					78	40		
Pavement Patching, Class B at East End of project (Existing 4 lane section) WEST BOUND												
638+70.00	6	6	8	8					78	40		
639+55.00	6	6	8	8					78	40		
639+94.00	6	6	8	8					78	40		
640+21.00	6	6	8	8					78	40		
		TOTAL:	248		68.0		207		1652	760	74	275

48203021			HOT-MIX ASPHALT SHOULDERS, 6"			SQ YD	35,052
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY
	FT			FT			SQ YD
HOT-MIX ASPHALT SHOULDERS							
69+00.00	10.0		77+00.00	10.0	LT	WB OUTSIDE SHOULDER	888.9
477+00.00	10.0		536+45.09	10.0	LT	WB OUTSIDE SHOULDER	6605.7
544+56.78	10.0		568+82.92	10.0	LT	WB OUTSIDE SHOULDER	2695.7
570+86.59	10.0		640+00.00	10.0	LT	WB OUTSIDE SHOULDER	7681.6
68+83.54	6.0		70+34.00	20.2	LT	WB GORE	219.0
71+32.83	8.0		77+00.00	8.0	LT	WB INSIDE SHOULDER	504.2
477+00.00	8.0		535+91.59	8.0	LT	WB INSIDE SHOULDER	5237.0
528+65.87	0.0		528+84.02	37.0	CT	MAINTENANCE CROSS OVER	15.7
528+84.02	37.0		529+15.98	37.0	CT	MAINTENANCE CROSS OVER	131.4
529+15.98	37.0		529+34.12	0.0	CT	MAINTENANCE CROSS OVER	15.7
535+91.59	8.0		536+60.71	6.0	LT	WB INSIDE SHOULDER	53.8
544+74.48	6.0		545+17.50	6	LT	WB INSIDE SHOULDER	28.7
545+17.50	6.0		545+77.50	8	LT	WB INSIDE SHOULDER	46.7
545+77.50	8.0		568+16.08	8	LT	WB INSIDE SHOULDER	1989.8
568+16.08	8.0		568+87.85	6	LT	WB INSIDE SHOULDER	55.8
570+92.17	6.0		571+34.00	6	LT	WB INSIDE SHOULDER	27.9
571+34.00	6.0		571+94.00	8	LT	WB INSIDE SHOULDER	46.7
571+94.00	8.0		640+00.00	8	LT	WB INSIDE SHOULDER	6049.8
629+00.00	10.0		633+93.41	10.0	LT	EB INSIDE SHOULDER	548.2
HOT-MIX ASPHALT SHOULDERS BEHIND GUARDRAIL							
504+61.34	3.0		508+78.84	3.0	LT	WB OUTSIDE SHOULDER	139.2
508+78.84	3.0		509+03.84	10.0	LT	WB OUTSIDE SHOULDER	18.1
509+03.84	10.0		509+28.84	10.0	LT	WB OUTSIDE SHOULDER	27.8
509+28.84	10.0		509+51.34	0.0	LT	WB OUTSIDE SHOULDER	12.5
536+30.43	3.0		536+57.59	3.0	LT	WB OUTSIDE SHOULDER	9.1
544+38.73	3.0		568+96.68	3.0	LT	WB OUTSIDE SHOULDER	819.3
570+71.18	3.0		577+89.93	3.0	LT	WB OUTSIDE SHOULDER	239.6
577+89.93	3.0		578+14.93	10.0	LT	WB OUTSIDE SHOULDER	18.1
578+14.93	10.0		578+39.93	10.0	LT	WB OUTSIDE SHOULDER	27.8
578+39.93	10.0		578+62.43	0.0	LT	WB OUTSIDE SHOULDER	12.5
536+51.59	3.0		536+78.76	3.0	LT	WB INSIDE SHOULDER	9.1
544+61.25	3.0		548+36.22	3.0	LT	WB INSIDE SHOULDER	125.0
548+36.22	3.0		548+61.15	10.0	LT	WB INSIDE SHOULDER	18.0
548+61.15	10.0		548+86.23	10.0	LT	WB INSIDE SHOULDER	27.9
548+86.23	10.0		549+08.73	0.0	LT	WB INSIDE SHOULDER	12.5
568+76.08	3.0		569+03.25	3.0	LT	WB INSIDE SHOULDER	9.1
570+77.75	3.0		574+59.05	3.0	LT	WB INSIDE SHOULDER	127.1
574+59.05	3.0		574+84.05	10.0	LT	WB INSIDE SHOULDER	18.1
574+84.05	10.0		575+09.05	10.0	LT	WB INSIDE SHOULDER	27.8
575+09.05	10.0		575+31.54	0.0	LT	WB INSIDE SHOULDER	12.5
EXISTING WB SHOULDER , 500 SQ YD							500
			TOTAL				35,052

T:\18914\Civil\PAV_Plans\20PAV\SCHED08.dgn

PARSONS BRINCKERHOFF
230 West Monroe St., Suite 900
Chicago, IL 60606, (312) 782-5160

USER NAME = MMS	DESIGNED - MMS	REVISED -	
	DRAWN - MMS	REVISED -	
PLOT SCALE = 50.0000 ' / IN.	CHECKED - RMH	REVISED -	
PLOT DATE = 9/28/11	DATE - 12/02/2011	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. 6 OF 16 SHEETS | STA. TO STA.

⚠ Rev. 2-22-12

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2-1	STEPHENSON	211	20
FINAL SUBMITTAL		CONTRACT NO. 64860		
	ILLINOIS	FED. AID PROJECT P-92-014-03		