

EARTHWORK SCHEDULE

LOCATION			MOT STAGES	EARTH EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 25%) (CU YD)	EMBANKMENT (CU YD)	ROCK EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION (CU YD)	TOPSOIL TO BE USED IN TOPSOIL PLACEMENT (ADJ. FOR SHRINKAGE 25%) (CU YD)	TOPSOIL PLACEMENT (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)
US 20 MAINLINE													
463+30.00	TO	471+00.00	STAGE IA	0	0	0	0	0	0	0	0	0	0
471+00.00	TO	473+25.00		0	0	0	0	0	0	0	0	0	0
637+30.00	TO	644+00.00		150	110	354	0	-244	123	92	123	-31	276
66+07.35	TO	71+00.00	STAGE I	1,131	848	1,827	0	-979	1,236	930	344	586	
71+00.00	TO	77+00.00		3,110	2,332	4,944	0	-2,612	4,665	3,500	504	2,996	
477+00.00	TO	486+00.00		1,519	1,139	170	0	970	0	0	266	-266	
486+00.00	TO	501+00.00		3,879	2,909	426	0	2,483	0	0	539	-539	
501+00.00	TO	516+00.00		2,770	2,077	686	0	1,391	0	0	678	-678	
516+00.00	TO	531+00.00		1,576	1,182	408	0	774	0	0	394	-394	
531+00.00	TO	546+00.00		664	498	202	0	296	0	0	192	-192	
546+00.00	TO	561+00.00		1,977	1,483	128	0	1,355	0	0	221	-221	
561+00.00	TO	576+00.00		759	569	280	0	289	0	0	300	-300	
576+00.00	TO	590+00.00		1,751	1,314	315	0	999	0	0	445	-445	
590+00.00	TO	604+00.00		1,080	810	530	0	280	0	0	467	-467	
604+00.00	TO	619+00.00		1,042	781	685	0	96	0	0	520	-520	3972
619+00.00	TO	634+00.00		3,145	2,359	1,712	2,036	2,682	536	400	770	-370	6518
634+00.00	TO	644+00.00		1	1	201	9,224	9,023	523	390	954	-564	1897
463+30.00	TO	471+00.00		* STAGE II	0	0	0	0	0	0	0		
471+00.00	TO	473+25.00	0		0	0	0	0	0	0			
637+30.00	TO	644+00.00	244		0	0	0	244	0	0			
TOTAL:				24,800	18,415	12,870	11,260	17,050	7,085	5,315	6,720	-1,410	12,665

NOTE:

- CONTRACTOR MAY ROUGH GRADE AND UTILIZE GRADE FROM STA. 501+00 TO 516+00 AND FROM STA. 634+00 TO 644+00 AS BORROW LOCATIONS FOR STAGE IA.
 - EXISTING TOP SOIL REMOVAL SHALL BE USED FOR 12" TOPSOIL PLACEMENT FOR ROCK CUT DITCHES AND BENCHES.
- * TEMPORARY PAVEMENT CONSTRUCTED IN STAGE 1A WILL BE REMOVED AND NECESSARY GRADING WILL BE DONE DURING THIS STAGE.

T:\181844\Civil\PAV_Plans\28P\A\earthwork.dgn



USER NAME = MMS	DESIGNED - MS	REVISED -
	DRAWN - MS	REVISED -
PLOT SCALE = 50.0000' / IN.	CHECKED - RH	REVISED -
PLOT DATE = 9/28/11	DATE - 12/02/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2-1	STEPHENSON	211	31
FINAL SUBMITTAL			CONTRACT NO. 64860	
ILLINOIS FED. AID PROJECT P-92-014-03				

Rev. 2-22-12