

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE		80% FEDERAL 20% STATE	
					0001	0008	0008	0008
					ROADWAY	US RTE 20 OVER PECAATONICA RIVER S.N. 089-0082	US RTE 20 OVER JANE ADDAMS TRAIL S.N. 089-0083	
	542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	88	88			
	5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	449	449			
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1			
	54215547	METAL END SECTIONS 12"	EACH	6	6			
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	51	51			
	60100080	FRENCH DRAINS	CU YD	39	39			
	60100945	PIPE DRAINS 12"	FOOT	234	234			
	60107600	PIPE UNDERDRAINS 4"	FOOT	23,053	23,053			
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	950	950			
	60240361	INLETS, TYPE B, WITH MEDIAN INLET (604101)	EACH	1	1			
	60900240	TYPE C INLET BOX, STANDARD 609006	EACH	3	3			
	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	3	3			
	60900515	CONCRETE THRUST BLOCKS	EACH	3	3			
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,137.5	2,137.5			
*	63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3,062.5	3,062.5			
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	10	10			
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	6	6			
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
*	63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	8	8			
	63200310	GUARDRAIL REMOVAL	FOOT	1,027	1,027			
	63500105	DELINEATORS	EACH	80	80			
	64200116	SHOULDER RUMBLE STRIPS, 16"	FOOT	64,423	64,423			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12			
	67100100	MOBILIZATION	L SUM	1	1			
	70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2			

△ NON-PARTICIPATING ITEM (100% STATE)
 • SPECIALTY ITEM

T:\168144\G\1\PAV_Plan\20\PAV5000.dgn

PARSONS BRINCKERHOFF
 250 West Monroe St. Suite 900
 Chicago, IL 60606, (312) 782-8160

USER NAME = MMS	DESIGNED - MMS	REVISED -
DRAWN - MMS	CHECKED - RMH	REVISED -
PLOT SCALE = 50.00' / IN.	DATE - 12/02/2011	REVISED -
PLOT DATE = 9/28/11		

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A. RTE. 301	SECTION 177-2-1	COUNTY STEPHENSON	TOTAL SHEETS 211	SHEET NO. 7
SCALE: NONE		SHEET NO. 3 OF 5 SHEETS		STA. TO STA.
FINAL SUBMITTAL			CONTRACT NO. 64860	
ILLINOIS FED. AID PROJECT P-92-014-03				