

X4400110		TEMPORARY PAVEMENT REMOVAL				SQ YD	1,300
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY
	FT			FT			SQ YD
463+30.00	5.0		466+10.68	5.0	RT	EASTBOUND	156
466+10.68	5.0		470+38.81	5.0	RT	EASTBOUND	238
470+38.81	5.0		473+25.00	5.0	RT	EASTBOUND	159
637+30.00	2.0		637+87.07	2.0	CT	CROSS OVER	13
637+87.07	2.0		639+62.85	16.0	CT	CROSS OVER	176
639+62.85	16.0		641+70.49	16.0	CT	CROSS OVER	369
641+70.49	16.0		643+48.31	2.0	CT	CROSS OVER	178
643+48.31	2.0		644+00.00	2.0	CT	CROSS OVER	11
TOTAL							1,300

X7240300		SIGN REMOVAL			EACH	1
STATION	OFFSET	LT/RT	TYPE	LOCATION	QUANTITY	
					EACH	
624+91.07	18.50	LT		WB INSIDE SHOULDER	1	
TOTAL						1

X7800605		URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS				SQ FT	84
STATION	OFFSET	TO	LT/RT	COLOR	DESCRIPTION	QUANTITY	
	FT					FOOT	
477+50.00	47		LT	WHITE	WB TRAVEL LANES	42	
482+50.00	49		LT	WHITE	WB TRAVEL LANES	42	
TOTAL							84

X7800610		URETHANE PAVEMENT MARKING - LINE 4"					FOOT	76,896
STATION	OFFSET	TO	STATION	OFFSET	LT/RT	COLOR	DESCRIPTION	QUANTITY
	FT			FT				FOOT
457+69.59	27		466+11.08	27	RT	WHITE	WB TRAVEL LANES	841
485+00.00	51		666+41.00	51	LT	WHITE	WB TRAVEL LANES	18,141
457+69.59	51		640+25.00	51	RT	WHITE	EB TRAVEL LANES	18,255
457+69.59	39		468+25.32	39	RT	YELLOW	EB/WB TRAVEL LANES	1,056
457+69.59	40		468+25.32	40	RT	YELLOW	EB/WB TRAVEL LANES	1,056
68+20.71	18		70+34.00	16	LT	DOUBLE YELLOW	GORE	427
70+34.00	16		72+63.90	24	RT	YELLOW	WB TRAVEL LANES	230
72+63.90	24		77+00.00	24	RT	YELLOW	WB TRAVEL LANES	436
468+25.32	39		471+38.61	39	RT	DOUBLE YELLOW	GORE	627
471+38.61	39		472+38.61	27	RT	DOUBLE YELLOW	TAPER	100
477+00.00	27		666+41.00	27	LT	YELLOW	WB TRAVEL LANES	18,941
472+38.61	27		640+25.00	27	RT	YELLOW	EB TRAVEL LANES	16,786
TOTAL								76,896

X7800630		URETHANE PAVEMENT MARKING - LINE 6"				FOOT	8,832
STATION	TO	STATION	LT/RT	RATIO	DESCRIPTION	QUANTITY	
						FOOT	
471+38.61		536+91.95	RT	0.25	EB TRAVEL LANES	1,638	
536+91.95		545+08.85	RT	0.25	EB TRAVEL LANES	204	
545+08.85		568+97.70	RT	0.25	EB TRAVEL LANES	597	
568+97.70		571+03.01	RT	0.25	EB TRAVEL LANES	51	
571+03.01		640+25.00	RT	0.25	EB TRAVEL LANES	1,730	
482+00.00		536+51.33	LT	0.25	WB TRAVEL LANES	1,363	
536+51.33		544+68.24	LT	0.25	WB TRAVEL LANES	204	
544+68.24		568+84.90	LT	0.25	WB TRAVEL LANES	604	
568+84.90		570+90.20	LT	0.25	WB TRAVEL LANES	51	
570+90.20		666+41.00	LT	0.25	WB TRAVEL LANES	2,388	
TOTAL							8,832

X7800640		URETHANE PAVEMENT MARKING - LINE 8"			FOOT	1,889
STATION	TO	STATION	LT/RT	COLOR	DESCRIPTION	QUANTITY
						FOOT
466+11.08		485+00.00	LT	WHITE	WB TRAVEL LANES	1,889
TOTAL						1,889

X7800650		URETHANE PAVEMENT MARKING - LINE 12"				FOOT	93
STATION	TO	STATION	LT/RT	COLOR	DESCRIPTION	QUANTITY	
						FOOT	
469+10.49		469+18.54	RT	YELLOW	GORE STRIPES	11	
469+37.88		469+48.47	RT	YELLOW	GORE STRIPES	15	
469+65.26		469+78.40	RT	YELLOW	GORE STRIPES	19	
469+92.64		470+08.33	RT	YELLOW	GORE STRIPES	22	
470+20.02		470+38.26	RT	YELLOW	GORE STRIPES	26	
TOTAL							93

X7830070		GROOVING FOR RECESSED PAVEMENT MARKING 5"					FOOT	31,690
STATION	OFFSET	TO	STATION	OFFSET	LT/RT	COLOR	DESCRIPTION	QUANTITY
	FT			FT				FOOT
485+00.00	51		536+45.09	51	LT	WHITE	WB TRAVEL LANES	5,145
544+61.99	51		568+82.92	51	LT	WHITE	WB TRAVEL LANES	2,421
570+88.23	51		640+00.00	51	LT	WHITE	WB TRAVEL LANES	6,912
466+11.08	39		468+25.32	39	RT	YELLOW	EB/WB TRAVEL LANES	214
466+11.08	40		468+25.32	40	RT	YELLOW	EB/WB TRAVEL LANES	214
68+20.71	18		70+34.00	16	RT	YELLOW	GORE	427
70+34.00	16		72+63.90	24	RT	YELLOW	WB TRAVEL LANES	230
72+63.90	24		77+00.00	24	RT	YELLOW	WB TRAVEL LANES	436
468+25.32	39		471+38.61	39	RT	YELLOW	GORE	313
471+38.61	39		472+38.60	27	RT	YELLOW	GORE	100
477+00.00	27		536+57.58	27	LT	YELLOW	WB TRAVEL LANES	5,958
544+74.48	27		568+86.87	27	LT	YELLOW	WB TRAVEL LANES	2,412
570+92.17	27		640+00.00	27	LT	YELLOW	WB TRAVEL LANES	6,908
TOTAL								31,690

PARSONS BRINCKERHOFF
 280 West Monroe St. Suite 900
 Chicago, IL 60606, (312) 782-8150

USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 13 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2-1	STEPHENSON	211	27
FINAL SUBMITTAL			CONTRACT NO. 64860	
[ILLINOIS] FED. AID PROJECT			P-92-014-03	