

X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"				FOOT	3,694
STATION	TO	STATION	LT/RT	RATIO	DESCRIPTION	QUANTITY
						FOOT
482+00.00		536+51.33	LT	0.25	WB TRAVEL LANES	1,363
544+68.24		568+84.90	LT	0.25	WB TRAVEL LANES	604
570+90.20		640+00.00	LT	0.25	WB TRAVEL LANES	1,727
TOTAL						3,694

Z0013796	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE			SQ YD	444
STATION	LT/RT	WIDTH	LENGTH	QUANTITY	
				FT	SQ YD
476+00.00	RT	20	40	89	
530+50.00	RT	20	40	89	
546+75.00	RT	20	40	89	
595+50.00	RT	20	40	89	
628+00.00	RT	20	40	89	
TOTAL				444	

X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"				FOOT	1,889
STATION	TO	STATION	LT/RT	RATIO	DESCRIPTION	QUANTITY
						FOOT
466+11.08		485+00.00	LT	1.00	WB TRAVEL LANES	1,889
TOTAL						1,889

Z0014700	CULVERT TO BE CLEANED		EACH	8
STATION	LT/RT	DESCRIPTION	LENGTH	QUANTITY
			FT	EACH
505+00.00	LT	EXISTING CULVERT	263	1
516+65.00	LT/RT	EXISTING CULVERT	169	1
528+00.00	LT	STORM SEWER	90	1
552+00.00	LT	STORM SEWER	82	1
572+00.00	LT	STORM SEWER	122	1
598+25.00	LT	STORM SEWER	101	1
601+50.00	LT	STORM SEWER	95	1
629+90.94	LT/RT	EXISTING CULVERT	63	1
TOTAL			8	

X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"				FOOT	93
STATION	TO	STATION	LT/RT	COLOR	DESCRIPTION	QUANTITY
						FOOT
469+10.49		469+18.54	RT	YELLOW	GORE STRIPES	11
469+37.88		469+48.47	RT	YELLOW	GORE STRIPES	15
469+65.26		469+78.40	RT	YELLOW	GORE STRIPES	19
469+92.64		470+08.33	RT	YELLOW	GORE STRIPES	22
470+20.02		470+38.26	RT	YELLOW	GORE STRIPES	26
TOTAL						93

Z0062456	TEMPORARY PAVEMENT					SQ YD	1,300
STATION	WIDTH	TO	STATION	WIDTH	LT/RT	DESCRIPTION	QUANTITY
						FT	SQ YD
463+30.00	5.0		466+10.68	5.0	RT	EASTBOUND	156
466+10.68	5.0		470+38.81	5.0	RT	EASTBOUND	238
470+38.81	5.0		473+25.00	5.0	RT	EASTBOUND	159
637+30.00	2.0		637+87.07	2.0	CT	CROSS OVER	13
637+87.07	2.0		639+62.85	16.0	CT	CROSS OVER	176
639+62.85	16.0		641+70.49	16.0	CT	CROSS OVER	369
641+70.49	16.0		643+48.31	2.0	CT	CROSS OVER	178
643+48.31	2.0		644+00.00	2.0	CT	CROSS OVER	11
TOTAL						1,300	

HMA SCHEDULE

STATIONS	REMARKS	LENGTH FT.	PROPOSED SURFACE AREAS		EXISTING SURFACE AREAS		31100910	31100935	31100965	31100975	40600200	40603310	40701956	48203021
			PAVEMENT	SHOULDER	SHOULDER	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE A 18"	SUBBASE GRANULAR MATERIAL, TYPE A 24"	SUBBASE GRANULAR MATERIAL, TYPE A 30"	BITUMINOUS MATERIALS PRIME COAT	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	HOT-MIX ASPHALT SHOULDERS, 6"	
			OVERALL AREA	BIT. AREA	BIT. AREA	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	SQ. YD.	SQ. YD.	
US 20														
66+07 - 77+00	MAINLINE	1,093	2,593	2,077	0	5,227	0	0	0	6.0	233	2,593	2,077	
477+00 - 536+81	MAINLINE	5,981	15,887	12,744	15,177	18,360	3,500	2,835	6,000	22.2	3,982	15,887	12,744	
544+38 - 569+20	MAINLINE	2,482	6,466	5,828	5,430	13,167	0	0	0	10.7	1,565	6,466	5,828	
570+61 - 640+00	MAINLINE	6,939	18,437	15,510	15,323	35,859	0	0	0	30.9	4,227	18,437	15,510	
GRAND TOTAL			43,383	36,159	35,931	72,613	3,500	2,835	6,000	69.7	10,007	43,383	36,160	

PARSONS BRINCKERHOFF
 280 West Monroe St. Suite 900
 Chicago, IL 60606, (312) 782-8150

USER NAME = MMS	DESIGNED - MMS	REVISED -
PLOT SCALE = 5/8" = 1' / IN.	DRAWN - MMS	REVISED -
PLOT DATE = 9/28/11	CHECKED - RMH	REVISED -
	DATE - 12/02/2011	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 14 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2-1	STEPHENSON	211	28
FINAL SUBMITTAL			CONTRACT NO. 64860	
[ILLINOIS] FED. AID PROJECT P-92-014-03				