

CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ACNHF	ACBHF			
				80% FED	80% FED / 20% STATE			
				20% STATE	BRIDGE 0014			
				ROADWAY 0004	SN 043-0002 SN 043-0003	SN 043-0004 SN 043-0005	SN 043-0006	SN 043-0007
44000400	GUTTER REMOVAL	FOOT	38	38				
44004000	PAVED DITCH REMOVAL	FOOT	14	14				
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,150	2,150				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	64	64				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	45	45				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4,815	4,815				
50102400	CONCRETE REMOVAL	CU YD	167.8		54.0	51.4	32.4	30.0
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2				
50104650	SLOPE WALL REMOVAL	SQ YD	7,036		2,023	3,342	400	1,271
50104701	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	2		2			
50104702	REMOVAL OF EXISTING CONCRETE DECK NO. 2	EACH	2			2		
50104703	REMOVAL OF EXISTING CONCRETE DECK NO. 3	EACH	1				1	
50104704	REMOVAL OF EXISTING CONCRETE DECK NO. 4	EACH	1					1
50105220	PIPE CULVERT REMOVAL	FOOT	208	208				
50157300	PROTECTIVE SHIELD	SQ YD	250				250	
50200100	STRUCTURE EXCAVATION	CU YD	1,200		410	405	174	211
50300225	CONCRETE STRUCTURES	CU YD	322.1		118.0	78.7	37.6	87.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2,141.8		606.3	810.6	337.1	387.8
50300260	BRIDGE DECK GROOVING	SQ YD	5,134		1,368	1,936	836	994
50300300	PROTECTIVE COAT	SQ YD	6,358		1,726	2,440	957	1,235
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	28,420		9,100	10,200	4,500	4,620
50500505	STUD SHEAR CONNECTORS	EACH	17,622		5,148	6,516	2,466	3,492
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	500,320		139,920	183,120	79,880	97,400
50800515	BAR SPLICERS	EACH	4,653		1,338	1,688	732	895
51100100	SLOPE WALL 4 INCH	SQ YD	400				400	
51500100	NAME PLATES	EACH	6		2	2	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	80					80
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	60		24	24	12	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12					12
52100510	ANCHOR BOLTS, 3/4"	EACH	48					48

* SPECIALTY ITEM
 Δ 100% STATE

USER NAME = #OPERATOR#	DESIGNED -	REVISED -
FILE NAME = #FILES#	CHECKED -	REVISED -
PLOT DATE = Thu Dec 08 14:12:42	DRAWN -	REVISED -
PLOT TIME = #TIME#	CHECKED -	REVISED -

WHKS & CO.
 ENGINEERING
 1701 ROUTE 35 NORTH
 EAST DUBUQUE, IL 61025
 (815) 747-8833
 DESIGN FIRM #184001038

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**US 20
 SUMMARY OF QUANTITIES**

SCALE: NTS SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(43B,44B,44HB,45B/D)	JO DAVIESS	309	6
CONTRACT NO. 64C94			Rev.	
ILLINOIS FED. AID PROJECT				