

LOCATION			TYPE	COLOR	70300100 SHORT TERM PAVEMENT MARKING	70300220 TEMPORARY PAVEMENT MARKING - LINE 4"	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	78008210 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	78008230 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	78008240 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	78100100 RAISED REFLECTIVE PAVEMENT MARKERS	78300100 PAVEMENT MARKING REMOVAL	78300100 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	STATION	OFFSET			(FOOT)	(FOOT)	(SQ.FT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(SQ.FT)	(EACH)
SN 043-0007													
PRE-STAGE													
482+06	492+42	CL											13
STAGE 1													
477+80	482+80	CL	SOLID	WHITE		500	167					167	
482+80	484+80	LT	SOLID	WHITE		200	67					67	
484+80	488+80	LT	SOLID	WHITE		400	133					134	
488+80	492+42	LT	SOLID	WHITE		362	121					121	
482+80	484+80	LT	SOLID	YELLOW		200	67					67	
484+80	488+80	LT	SOLID	YELLOW		400	133					134	
488+80	490+10	LT	SOLID	YELLOW		130	43					44	
STAGE 2													
477+80	482+80	CL	SOLID	YELLOW		500	167						
482+80	490+80	RT	SOLID	YELLOW		800	267						
482+80	490+80	RT	SOLID	WHITE		800	267						
STAGE 3													
477+80	482+06	CL	SKIP DASH	WHITE	64		21						
482+06	492+42	CL	SKIP DASH	WHITE	148		49						
STAGE 4													
477+80	482+06	CL	SKIP DASH	WHITE					110				
482+06	492+42	LT	SOLID	YELLOW			1,036						
482+06	492+42	CL	SKIP DASH	WHITE					260		13		
482+06	492+42	RT	SOLID	WHITE			1,036						
SUBTOTAL					212	4,292	1,502	2,072	370	0	13	734	13
TOTALS					1,264	32,390	11,220	12,087	2,850	160	71	4,438	70