CONCRETE SCHEDULE (CONTINUDED)

LOCATION	QUADRANT	SUGGESTED METHOD	CC&G REM FOOT	CC&G TYPE, B-6.18 FOOT	SIDEWALK REM SQ FT	PCC SIDEWALK 4IN. SQ FT	PCC SIDEWALK 8IN. SQ FT	DETECT WARN SQ FT	MEDIAN REM SQ FT	SODDING SALT TOLERANT SQ YD	NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND
ST. JOSEPH AVENUE	NW	424011	20.0	20.0	100.0	100.0		20.0		0.0	0.0	0.0	0.0
	NE	424011	20.0	20.0	118.8	118.8		20.0		0.0	0.0	0.0	0.0
HAMMES AVENUE	NW	424011	23.0	23.0	92.0	92.0		16.0		0.0	0.0	0.0	0.0
	NE	424001	0.0	0.0	35.0	35.0		10.0		0.0	0.0	0.0	0.0
SB EXIT/ENTRANCE RAMP I-57	NW	424001	0.0	0.0	35.0	35.0		10.0		2.0	0.0	0.0	0.0
SB EXIT/ENTRANCE RAMP I-57	NE	424011	40.0	40.0	200.0		200.0	20.0		9.0	0.1	0.1	0.1
NB EXIT/ENTRANCE RAMP I-57	SW	424001	0.0	0.0	36.0	36.0		12.0		3.0	0.0	0.0	0.0
NB EXIT/ENTRANCE RAMP I-57	CENTER					30.0		10.0	30.0				
NB EXIT/ENTRANCE RAMP I-57	SE	424001	0.0	0.0	40.0	40.0		10.0		3.0	0.0	0.0	0.0
FRONTAGE ROAD	NW	424001	7.0	7.0	20.0	20.0		8.0		3.0	0.0	0.0	0.0
EASTRIDGE DRIVE	SW	424011	27.0	27.0	145.0	145.0		24.0		3.0	0.0	0.0	0.0
SUBTOTAL			137.00	137.00	821.75	651.75	200.00	160.00	30.00	23.00	0.29	0.29	0.29
TOTALS			1352.0	1352.0	10344.0	10149.0	200.0	1733.0	30.0	266.0	4.0	4.0	4.0

PAVEMENT MARKING

STATION	~~70300100~~ SHORT TERM PAVT MARK 4 IN FOOT	~~78003100~~ PREF PLASTIC PAVT MRK TYPE B L&S SQ FT	~~78000200~~ THERMO PLASTIC MRK 4 IN FOOT	~~78004230~~ PREF PLASTIC PAVT MRK INLAID 6 IN FOOT	~~78000500~~ THERMO PLASTIC MRK 8 IN FOOT	~~78000600~~ THERMO PLASTIC MRK 12 IN FOOT	~~78003180~~ PREF PLASTIC PAVT MRK TYPE B 24 IN FOOT	~~X7800610~~ URETHANE PAVT MRK 4 IN FOOT	~~X7800640~~ URETHANE PAVT MRK 8 IN FOOT	~~X7800650~~ URETHANE PAVT MRK 12 IN FOOT	~~X7830074~~ GROOVE RECESSED PAVT MRK 7 IN FOOT	~~X7830076~~ GROOVE RECESSED PAVT MRK 9 IN FOOT	~~78100100~~ RAISED REFLECT MARK EACH
STA. 138+00 - 139+14	63	15.6	166	443	46	428	60					46	2
STA. 139+14 - 142+25	434	93.6	774	156	380	0	83					380	42
STA. 142+25 - 146+11	354	62.4	750	575	277	414	110					277	37
STA. 146+11 - 150+03	354	62.4	862	700	180	552	135					180	36
STA. 150+03 - 152+00	292	114.4	434	677	173	625	93					173	15
STA. 152-00 - 159+00	0	0.0	0	634	0	0	14	1713	118	342	634	118	31
STA. 159+00 - 164+11	510	93.6	1137	741	306	524	120					306	51
STA. 164+11 - 167+85	402	0.0	1400	405	0	420	29					0	30
STA. 167+85 - 171+84	371	62.4	794	730	272	520	132					272	41
STA. 171+84 - 175+81	411	46.8	1114	687	170	608	77					170	33
STA. 175+81 - 179+66	343	62.4	782	723	163	286	68					163	39
STA. 179+62 - 183+58	340	62.4	1053	712	0	270	63					0	32
STA. 183+58 - 187+42	339	62.4	990	568	0	130	28					0	32
STA. 187+46 - 195+27	695	124.8	1828	984	0	136	42					0	68
STA. 195+27 - 199+67	400	62.4	1399	385	118	0	24					118	38
STA.199+67 - 210+75	912	347.6	3187	1550	51	484	78					51	95
STA. 210+75 - 221+01	841	232.8	3297	1342	289	274	191					289	78
STA. 221+17 - 234+50	1555	357.6	6034	1403	504	406	197					504	133
STA. 234+50 - 249+19.06	1543	421.2	3687	1142	925	572	340					925	128
SQ 249+19.06=3+83.36													
STA.3+83.36 - 18+50	1392	62.4	3372	684	390	132	155					390	106
STA.18+50 - 65+00	3826	31.2	19143	2303	906	0	96					906	481
TOTALS	15,377	2378.4	52,203	17,544	5,150	6,781	2,135	1,713	118	342	634	5,268	1,548

NOTE: LOCATION STATION 152+00 - 159+00 HAS 31 EACH RAISED REFLECTOR MARKERS SET IN CONCRETE PAVEMENT AND NEEDS TO BE REMOVED AND REPLACED IN ACCORDANCE WITH SECTION 783 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION BOOK.