

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				KANKAKEE CO.	IROQUOIS CO.
				ROADWAY 0005 RURAL	ROADWAY 0005 RURAL
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12,656	2562	10,094
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	521	148	373
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	909	909	0
42400800	DETECTABLE WARNINGS	SQ FT	120	120	0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	152970	31823	121147
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12975	12975	0
44000600	SIDEWALK REMOVAL	SQ FT	855	855	0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	398	0	398
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	20	0	20
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	27	0	27
48101200	AGGREGATE SHOULDER, TYPE B	TON	2457	349	2108
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8	0
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	9	1	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	0.8	3.2



• SPECIALTY ITEMS

Rev. 2-22-12

FILE NAME =	USER NAME = corcoran	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwork\pwork\corcoran\0135018\066921-shr-S00.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	332	(4,5,H,K,C-1)RS-4	20	4
		CHECKED -	REVISED -									KANKAKEE & IROQUOIS		
		DATE -	REVISED -									ILLINOIS FED. AID PROJECT		