

80% FED.  
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				KANKAKEE CO.	IROQUOIS CO.
				ROADWAY 0005 RURAL	ROADWAY 0005 RURAL
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12,656	2562	10,094
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	521	148	373
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	909	909	0
42400800	DETECTABLE WARNINGS	SQ FT	120	120	0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	152970	31823	121147
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	12975	12975	0
44000600	SIDEWALK REMOVAL	SQ FT	855	855	0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	398	0	398
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	20	0	20
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	27	0	27
48101200	AGGREGATE SHOULDER, TYPE B	TON	2457	349	2108
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8	0
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	9	1	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	0.8	3.2



• SPECIALTY ITEMS

Rev. 2-22-12

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwork\pwidth\corcoran\m\0135018\066921-shr-S00.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	332	(4,5,H,K,C-1)RS-4	20	4
		CHECKED -	REVISED -									KANKAKEE & IROQUOIS		
		DATE -	REVISED -									ILLINOIS FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				KANKAKEE CO.	IROQUOIS CO.
				ROADWAY 0005 RURAL	ROADWAY 0005 RURAL
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	978	978	0
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	524	524	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	180	180	0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	193,748	24,640	169,108
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	24,036	3080	20,956
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	89	89	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	694	172	522
78200300	PRISMATIC CURB REFLECTOR	EACH	15	15	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	550	157	393
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	116	116	0
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	118	118	0
Z0021700	EXPANSION JOINT REHABILITATION	FOOT	230	0	230
Z0034105	MATERIAL TRANSFER DEVICE	TON	12,656	2562	10,094
Z0055300	RUMBLE STRIP	EACH	1	0	1
② Z0076600	TRAINEES	HOUR	1000	1000	

② 0042  
 \* SPECIALTY ITEMS

△ Rev. 2-22-12

FILE NAME =	USER NAME = cccorenlm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pvidot\cccorenlm\0135018\066921-sht-500.dgn		DRAWN -	REVISED -		332	(4,5,H,K,C-1)RS-4		20	6				
PLOT SCALE = 100.0000" = 1"		CHECKED -	REVISED -		* KANKAKEE & IROQUOIS				CONTRACT NO. 66921				
PLOT DATE = 12/13/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.						