

SUMMARY OF QUANTITIES													
CODE NO	ITEM	UNIT	90% FED - 10% STATE TOTAL QTY	CONSTRUCTION TYPE CODE									
				RURAL RDWY	URBAN RDWY	050-0223 URBAN	050-0127 RURAL	050-0129 RURAL	050-0222 RURAL	050-0130 URBAN	050-2509 URBAN	050-0216 URBAN	050-0089 RURAL
				0004	0004	0014	0014	0014	0014	0014	0014	0014	0014
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14,086	10767	5319								
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	32,855	22555	10330								
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	38936	10538	28398								
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	91,205	78064	15,141								
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	11365		11365								
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	120,667	101024	19,643								
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SQ YD	88000	29273	58727								
44000178	HOT-MIX ASPHALT SURFACE REMOVAL, 7 1/4"	SQ YD	130,722	109442	21,280								
44000189	HOT-MIX ASPHALT SURFACE REMOVAL, 10"	SQ YD	14386	4684	9702								
44000194	HOT-MIX ASPHALT SURFACE REMOVAL, 11 1/4"	SQ YD	40,222	33675	6547								
44004000	PAVED DITCH REMOVAL	FOOT	351		351								
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	627	208	419								
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	69		69								
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	140	93	47								
44201299	DOWEL BARS 1 1/2"	EA	1240	440	800								
44213100	PAVEMENT FABRIC	SQ YD	209	93	116								
44213200	SAW CUTS	FOOT	4299	1364	2935								
44213204	TIE BARS 3/4"	EACH	86	35	51								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5512	3735	1777								
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1931	778	1153								
48203027	HOT-MIX ASPHALT SHOULDERS, 7 1/2"	SQ YD	13164	3466	9698								
48203031	HOT-MIX ASPHALT SHOULDERS, 8 1/2"	SQ YD	36,936	34687	2269								
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	306		306								
50102400	CONCRETE REMOVAL	CU YD	13.5								13.5		
50104650	SLOPE WALL REMOVAL	SQ YD	73								73		
50157300	PROTECTIVE SHIELD	SQ YD	754			240	240			274			
50200100	STRUCTURE EXCAVATION	CU YD	100								100		
50300225	CONCRETE STRUCTURES	CU YD	24.2			1.4		1.5			4.9	16.4	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5418			213		223			2690	659	1633
54003000	CONCRETE BOX CULVERTS	CU YD	37.6	6.4							31.2		
60600605	CONCRETE CURB, TYPE B	FOOT	150	105	45								
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FT. POSTS	FOOT	6399	1443	4956								
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	64	64									
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	2	7								
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	14	7	7								
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	16	9	7								
63200310	GUARDRAIL REMOVAL	FOOT	5797	2473	3324								
* 63500105	DELINEATORS	EACH	479	186	293								

* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL#	PLOT SCALE = #SCALE#	DRAWN -	REVISED -			FAI-80/50-2, 4RS-5 & (50-3)RS-6	LA SALLE	109	4	
	PLOT DATE = #DATE#	CHECKED -	REVISED -			CONTRACT NO. 66A48				
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				

Rev.

SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____