

80% FED. / 20% STATE

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	ROADWAY 0005			
		UNIT	TOTAL QUANTITY	URBAN	RURAL
20101700	SUPPLEMENTAL WATERING	UNIT	2	2	
20400800	FURNISHED EXCAVATION	CU YD	16	12	4
25200110	SODDING, SALT TOLERANT	SQ YD	72	72	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15524	9664	5860
40600300	AGGREGATE (PRIME COAT)	TON	239	149	90
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	34	21	13
40600525	LEVELING BINDER (HAND METHOD), N50	TON	57	35	22
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0
40600990	TEMPORARY RAMP	SQ YD	200	176	24
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4920	3018	1902
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9840	6036	3804
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	669	539	130
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	574	574	
42400800	DETECTABLE WARNINGS	SQ FT	161	161	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	113730	69763	43967
44000600	SIDEWALK REMOVAL	SQ FT	574	574	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5471	2968	2503
56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4	
60255500	MANHOLES TO BE ADJUSTED	EACH	17	17	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	50	28	22
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	3.0	2.0
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1.0	
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1.0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11063	7106	3957

80% FED. / 20% STATE

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	ROADWAY 0005			
		UNIT	TOTAL QUANTITY	URBAN	RURAL
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	328	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67438	41058	26380
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	17166	11768	5398
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1366	1366	0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1274	1274	0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	468	468	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1131	692	439
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	312	312	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8542	8542	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1722	1722	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1366	1366	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1274	1274	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	468	468	
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	16	16	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	58892	32512	26380
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	15544	10146	5398
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	222	222	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	543	378	165
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	543	378	165
88600100	DETECTOR LOOP, TYPE I	FOOT	2694	2694	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5822	4676	1146
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	154	154	
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	150	150	
Z0034105	MATERIAL TRANSFER DEVICE	TON	14760	9054	5706
Z0076600	TRAINEES	HOURL	1000	1000	

*SPECIALTY ITEMS
00042