

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE CONSTR. CODE
				0005 ROADWAY
20400800	FURNISHED EXCAVATION	CU YD	38	38
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3
25200110	SODDING, SALT TOLERANT	SQ YD	232	232
25200200	SUPPLEMENTAL WATERING	UNIT	4	4
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3794	3794
40600300	AGGREGATE (PRIME COAT)	TON	67	67
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13
40600525	LEVELING BINDER (HAND METHOD), N50	TON	16	16
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	1215	1215
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	879	879
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2557	2557
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	375	375
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5854	5854
42400800	DETECTABLE WARNINGS	SQ FT	805	805
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4247	4247
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	28801	28801
44000300	CURB REMOVAL	FOOT	478	478
44000600	SIDEWALK REMOVAL	SQ FT	5854	5854
56109210	WATER VALVES TO BE ADJUSTED	EACH	1	1
60255500	MANHOLES TO BE ADJUSTED	EACH	37	37
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	15	15
60260100	INLETS TO BE ADJUSTED	EACH	25	25
60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	9

FILE NAME =	USER NAME = quigleyml	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\idot\quigleyml\d8253613\0365816-sht-details.DGN		DRAWN -	REVISED -						587	(20X) RS-2	LA SALLE		3
PLOT SCALE = 50.0000' / 1" =		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66B16				
PLOT DATE = 12/2/2011		DATE -	REVISED -						ILLINOIS FED. AID PROJECT				