

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE ROADWAY 0040 URBAN
20200100	EARTH EXCAVATION	CU YD	75	75
20400800	FURNISHED EXCAVATION	CU YD	181	181
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	175	175
48101200	AGGREGATE SHOULDERS, TYPE B	TONS	8	8
50102400	CONCRETE REMOVAL	CU YD	13.5	13.5
50200100	STRUCTURE EXCAVATION	CU YD	106	106
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1560	1560
54003000	CONCRETE BOX CULVERTS	CU YD	13.5	13.5
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	38	38
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	100	100
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	100	100
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	32	32
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	18	18
Z0015500	DEBRIS REMOVAL	L SUM	1	1
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2
Z0030370	IMPACT ATTENUATORS, RELOCATE (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	576	576

•SPECIALITY ITEMS

FILE NAME =	USER NAME = petelijj	DESIGNED - YOGESH PATEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. VAR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\p1dat\petelijj\d266589\036642-sheets.dgn	DRAWN - YOGESH PATEL	REVISED -	VARIOUS			VARIOUS	40	3		
PLOT SCALE = 100.0000 / / in.	CHECKED - RON WOODSHANK	REVISED -	CONTRACT NO. 66B42							
PLOT DATE = 12/27/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____						