

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE
				100%
				ROADWAY
				0005
				RURAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1262	1262
40600300	AGGREGATE (PRIME COAT)	TON	19	19
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	4	4
40600990	TEMPORARY RAMP	SQ YD	136	136
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	693	693
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17	17
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8220	8220
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	26	26
48101200	AGGREGATE SHOULDERS, TYPE B	TON	30	30
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	30	30
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3129	3129
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	313	313

FILE NAME =	USER NAME = petelyj	DESIGNED - RON WOODSHANK	REVISED -
c:\pwork\pedit\petelyj\d026941\N03668	B-sh-t-details.dgn	DRAWN - RON WOODSHANK	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	REVISED -
PLOT DATE = 12/22/2011	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 2 SHEETS STA. 351+58 TO STA. 367+18

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	D3 INTERMITTENT RS 2012-1	DEKALB	12	3
			CONTRACT NO. 66B45	
ILLINOIS FED. AID PROJECT				