



- ① PAVEMENT MARKING REMOVAL
- ② TEMPORARY PAVEMENT MARKING



- R2-1106-3618
- W2-1113(O)-3612
- R2-1-3648
- W2-1115(O)-3618

SYMBOLS

- ↑ Arrow board
- ▨ Work area
- ⊥ Sign
- ⬆ Direction indicator barricade with steady burn monodirectional light
- ⬇ Type II barricade, drum, or vertical barricade with steady burn monodirectional light
- ▬ Temporary concrete barrier
- ◁ Monodirectional barrier wall/guardrail marker
- ▣ Impact attenuator
- Flagger

- ① Temporary pavement marking tape shall be placed throughout the taper and along-side the work area. The right edge line shall be white and the left edge line shall be yellow.
- ② Barrier wall/guardrail markers at 25' (7.6 m). Markers on right shall be shall be crystal and markers on left shall be amber.
- ③ Vertical barricades shall not be used in lane shift taper.

SEQUENCE OF OPERATIONS

PASSING LANE SHALL BE CLOSED FOR STAGE I REMOVAL/CONSTRUCTION OPERATIONS.
 DRIVING LANE SHALL BE CLOSED FOR STAGE II REMOVAL/CONSTRUCTION OPERATIONS.

GENERAL NOTES

This standard is used where at any time any vehicle, equipment, workers or their activities will encroach on the pavement or on the shoulder within 24 (600) of the edge of pavement for daylight operation exceeding one day and where temporary concrete barrier is utilized.
 This Standard must always be used in combination with Standard 701400 (Special).
 When work is being performed in the left lane, the set up would be a mirror image to what is shown.
 Temporary concrete barrier shall be according to Standard 704001.
 Flaggers and Flagger signs shall be required whenever temporary concrete barrier is not in place. The flaggers shall be in constant communication and supplied with two-way radios or other approved devices.

| | | | |
|--|---------------------|--------------------------|-----------|
| FILE NAME = | USER NAME = patelij | DESIGNED - RON WOODSHANK | REVISED - |
| cr:\pwork\psidot\patelij\d0268336\0366848-sht-detail.dgn | | DRAWN - RON WOODSHANK | REVISED - |
| PLOT SCALE = 180,0000 / in. | | CHECKED - | REVISED - |
| PLOT DATE = 12/22/2011 | | DATE - | REVISED - |

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL AND PROTECTION,
 STANDARD 701402 (SPECIAL)
 SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

| | | | | |
|---------------------------|--------------|------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 95 | (53-5B-1)I-2 | LIVINGSTON | 16 | 6 |
| CONTRACT NO. 66B48 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |