SUMMARY OF QUANTITIES

	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION TYPE CODE: 0003 FED/STATE 80/20	0028 MULTI-USE PATHWAY FED/ST/CITY 80/10/10	0021 SIGNALS 80/10/10 FED STATE CITY	0040 CITY 100%	0040 FED/ST/CITY 80/10/10	0021 FED/STATE 80/20 URBAN
*	87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1,570			1,570			
*	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1			1			
*	87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1			1	1		
*	87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1			1			
*	87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1			1			
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5			
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	70.5			56			14.5
*	87900200	DRILL EXISTING HANDHOLE	EACH	2						2
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6			6			
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2			
*	88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	4			4			
*	88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4			4			
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1			
*	88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	4			4			
*	88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	10			10			
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	12			12			
*	88600100	DETECTOR LOOP, TYPE I	FOOT	1,505			1,433			72
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8			
*	X89000~~0~~8	TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL)	EACH	1			1			
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1			
*	89502380	REMOVE EXISTING HANDHOLE	EACH	1			1			
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1			1			
	Z0007126	HANDRAIL REMOVAL	FOOT	35	35					
	Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1					
	Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	477	477					
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
	Z0022800	FENCE REMOVAL	FOOT	697	697					
	Z0023600	FILLING EXISTING CULVERTS	EACH	3	3					
	Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 2	EACH	13	13					
	Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	12	12					
*	Z0033052	COMMUNICATIONS VAULT	EACH	10						10
*	Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1	1					
*	Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1	1					

* SPECIALTY ITEMS

1 REVISED 2/24/12

FILE NAME	USER NAME = 1007	DESIGNED	REVISED
		DRAWN	REVISED
	PLOT SCALE = 2.222 FT / IN.	CHECKED	REVISED
	PLOT DATE = 12/27/2011	DATE 10-21-11	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 399 (IL. RTE. 8)
SUMMARY OF QUANTITES

SCALE: NONE | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36 R-7	TAZEWELL	390	10

CONTRACT NO. 68370

ILLINOIS FED. AID PROJECT