

HANDRAIL REMOVAL
LOCATION SCHOOL STREET
STA. 12+72.20 TO STA. 12+83.20 RT 35
TOTAL 35

REMOVING INLETS
LOCATION ILLINOIS ROUTE 8
STA. 209+78.67 LT 1
STA. 214+89.44 LT 1
STA. 214+89.85 LT 1
STA. 224+81.48 RT 1
STA. 225+84.08 RT 1
STA. 228+12.70 RT 1
STA. 232+82.88 RT 1
TOTAL 7

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
LOCATION ILLINOIS ROUTE 8
EST. DEPTH EST. WIDTH CUYD
STA. 222+55 TO STA. 225+20 2' 74.1 1,404
TOTAL 9,128

\* UNSUITABLE MATERIAL THESE LOCATIONS TO BE REPLACED WITH EMBANKMENT
\*\* QUANTITY PROVIDED FOR INFORMATION ONLY - SEE EARTHWORK SUMMARY FOR AVAILABLE EMBANKMENT

TEMPORARY EROSION CONTROL SEEDING
LOCATION ILLINOIS ROUTE 8
SCHOOL STREET
TOTAL 660

TEMPORARY DITCH CHECKS
STAGE I LOCATION ILL. ROUTE 8
FEET
TOTAL 322

INLET AND PIPE PROTECTION
STAGE I LOCATION ILL. ROUTE 8
EACH
TOTAL 63

INLET AND PIPE PROTECTION
STAGE III LOCATION ILL. ROUTE 8
EACH
TOTAL 147

FENCE REMOVAL
LOCATION ILLINOIS ROUTE 8
STA. 239+18.40 TO STA. 239+68.40 LT 108
TOTAL 687

NITROGEN FERTILIZER NUTRIENT
LOCATION ILLINOIS ROUTE 8
SCHOOL STREET
TOTAL 891

PHOSPHORUS FERTILIZER NUTRIENT
LOCATION ILLINOIS ROUTE 8
SCHOOL STREET
TOTAL 891

POTASSIUM FERTILIZER NUTRIENT
LOCATION ILLINOIS ROUTE 8
SCHOOL STREET
TOTAL 891

BUILDING REMOVAL
LOCATION NO. 1
STA. 281+00.00 LT 1
TOTAL 1

REMOVAL AND DISPOSAL OF ASBESTOS, BUILDING NO. 1
FRIABLE L SUM 1
NON-FRIABLE L SUM 1

TOPSOIL SUMMARY
LOCATION MAINLINE STATION 240+00 TO 243+50 - 18" DEPTH
TOPSOIL EXCAVATION AND PLACEMENT CUYD
TOTAL 1,660

RIPRAP SCHEDULE
LOCATION SCHOOL STREET
AT DRAINAGE STRUCTURE 123B
4 LOCATIONS AT MEADOWVIEW LN.
TOTAL 68

EROSION CONTROL BLANKET
LOCATION ILLINOIS ROUTE 8
STA. 218+00 LT TO STA. 222+00 LY 584
TOTAL 1,078

SCHOOL ST.
STAGE I SUB-TOTAL 322
STAGE II LOCATION ILL. ROUTE 8
STAGE III LOCATION ILL. ROUTE 8
TOTAL 621

SCHOOL STREET
STAGE I SUB-TOTAL 63
STAGE II LOCATION ILL. ROUTE 8
TOTAL 147

SCHOOL STREET
STAGE III SUB-TOTAL 84
TOTAL 147

TEMPORARY RAMP
LOCATION SCHOOL ST
STA 3+63.25
TOTAL 148.0

REVISION 2/24/12

FILE NAME X:\Projects\288083565\001\04-Rte8-shl-5
USER NAME jdo1
DESIGNED DRAWN CHECKED DATE 10-21-11

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP 399 (IL RTE. 8) SCHEDULE OF QUANTITIES
SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 399
SECTION 36 R-7
COUNTY TAZEWELL
TOTAL SHEETS 390 SHEET NO. 21
CONTRACT NO. 68370
ILLINOIS FED. AID PROJECT