

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				FED/STATE 80/20	0028 MULTI-USE PATHWAY FED/ST/CITY 80/10/10	0021 ⁰¹ SIGNALS 80/10/10 FED STATE CITY	0040 CITY 100%	0040 FED/ST/CITY 80%/10%/10%	0021 ⁰² FED/STATE 80% 20% URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	338	338					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	496	496					
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25					
20200100	EARTH EXCAVATION	CU YD	24,800	24,800					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9,128	9,128					
20800150	TRENCH BACKFILL	CU YD	38	38					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	12,022	12,022					
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,660	1,660					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5,908	5,908					
* 25000210	SEEDING, CLASS 2A	ACRE	3.50	3.50					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,884	1,884					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,884	1,884					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,884	1,884					
25100115	MULCH, METHOD 2	ACRE	3.50	3.50					
25100630	EROSION CONTROL BLANKET	SQ YD	1,078	1,078					
25200110	SODDING, SALT TOLERANT	SQ YD	17,172	17,172					
25200200	SUPPLEMENTAL WATERING	UNIT	154.7	154.7					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,396	1,396					
28000305	TEMPORARY DITCH CHECKS	FOOT	621	621					
28000400	PERIMETER EROSION BARRIER	FOOT	14,260	14,260					
28000500	INLET AND PIPE PROTECTION	EACH	147	147					
28100105	STONE RIPRAP, CLASS A3	SQ YD	66	66					
28200200	FILTER FABRIC	SQ YD	66	66					
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	57,393	57,393					
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	8,015	8,015					
35101400	AGGREGATE BASE COURSE, TYPE B	TON	526	526					
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	4,461	4,461					
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	96	96					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	795	795					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1,410	1,410					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	184	184					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	971	971					

* SPECIALTY ITEMS

USER NAME: [blank] USER ID: [blank] USER TITLE: [blank]	DESIGNED: [blank] DRAWN: [blank] CHECKED: [blank] DATE: 10-21-11	REVISED: [blank] REVISED: [blank] REVISED: [blank]	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 399 (IL RTE. 8) SUMMARY OF QUANTITIES	F.A.P. RTE. 399 SECTION 36 R-7 COUNTY TAZEWELL TOTAL SHEETS 390 SHEETS NO. 5 CONTRACT NO. 68370 ILLINOIS FED. AID PROJECT
---	---	--	---	--	---