TREE REMOVAL, UNITS			
LOCATION		6 - 15 UNITS	OVER 15 UNITS
ILLINOIS ROUTE 8			
STA. 226+75.20	LT	12	
STA. 233+67.30	RT		20
STA. 237+21.30	RT		17
STA. 239+29.20	LT		42
STA. 239+86.70	LT		16
STA. 240+89.60	RT		40
STA. 241+45.70	LT	8	
STA. 241+54.20	LT	12	
STA. 241+80.00	RT		36
STA. 242+87.40	LT	6	
STA. 242+97.80	LT	6	
STA. 243+09.50	LT	6	
STA. 243+19.40	LT	6	
STA. 244+27.60	LT		30
STA. 247+37.40	RT		18
STA. 247+95.70	RT		24
STA. 248+69.10	RT		15
STA. 249+36.80	LT		16
STA. 250+24.40	LT		36
STA. 250+45.80	LT		54
STA. 251+33.30	LT	8	
STA. 251+42.60	LT	6	
STA. 251+47.10	RT	12	
STA. 251+52.90	LT	12	
STA. 251+58.40	LT	6	
STA. 251+84.10	LT	6	
STA. 252+22.20	LT		26
STA. 252+57.00	LT		26
STA. 252+91.10	LT		21
STA. 254+37.50	RT		15
STA. 255+46.30	LT	8	
STA. 255+56.70	LT	12	
STA. 255+59.50	LT	6	
STA. 255+69.70	LT	8	
STA. 255+78.80	LT	6	
STA. 255+92.80	LT	6	
STA. 255+97.80	LT	8	
STA. 256+17.70	LT	12	
STA. 256+46.70	LT	7	
STA. 256+59.00	LT	14	
STA. 256+62.10	LT	12	
STA. 256+63.20	LT	15	
STA. 256+70.70	LT	8	
STA. 256+73.60	LT	8	
STA. 256+73.80	LT	14	
STA. 256+88.50	LT	8	
STA. 256+97.00	LT	9	
STA. 257+39.70	LT		26
STA. 258+11.80	RT	9	
STA. 258+16.70	LT		18
STA. 258+25.30	RT	8	
STA. 258+30.70	RT	8	
STA. 258+43.50	RT	7	
STA. 258+63.00	LT	6	
STA. 258+76.40	LT	8	
STA. 258+88.00	LT	7	
SCHOOL STREET			
STA. 13+89.50	RT	6	
STA. 14+26.20	RT	6	
STA. 14+52.80	RT	6	
TOTAL		338	496

TREE REMOVAL, ACRES					
LOCATION					ACRES
ILLINOIS ROUTE 8					
STA. 255+55.10	LT	TO	STA. 256+23.60	LT	0.020
STA. 257+87.30	LT	TO	STA. 259+86.50	LT	0.100
				SUBTOTAL	0.120
				TOTAL (TO NEAREST 0.25)	0.250

SIDEWALK REMOVAL				
LOCATION				SQ FT
ILLINOIS ROUTE 8				
STA. 201+29.30	TO	STA. 201+36.00	RT	48
			TOTAL	48

MEDIAN REMOVAL				
LOCATION				SQ FT
ILLINOIS ROUTE 8				
STA. 271+60.00	TO	STA. 271+88.00	LT/RT	174
			TOTAL	174

CONCRETE HEADWALL REMOVAL		
LOCATION		EACH
ILLINOIS ROUTE 8		
STA. 209+77.15	RT	1
STA. 209+77.20	LT	1
STA. 214+16.35	LT	1
STA. 215+16.11	LT	1
STA. 215+77.23	RT	1
STA. 215+77.24	LT	1
STA. 232+15.78	LT	1
STA. 254+91.66	RT	1
TOTAL		8

CURB AND GUTTER REMOVAL				CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL
LOCATION				FOOT	FOOT
ILLINOIS ROUTE 8					
STA. 201+30.50	TO	STA. 202+29.00	LT	102	
STA. 202+37.00			LT	5	
STA. 208+97.50	TO	STA. 209+10.50	RT		13
STA. 214+59.63	TO	STA. 214+69.67	RT		89
STA. 214+60.00	TO	STA. 214+69.35	LT		90
STA. 269+30.00	TO	STA. 271+95.00	RT		244
STA. 271+19.00	TO	STA. 271+95.00	LT/RT		81
			TOTAL	107	517

EARTHWORK SUMMARY	VOLUME CUBIC YARDS			
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
MAINLINE STATION 200+00 TO 228+00	10,404.38	8,323.51	3,669.20	4,654.31
MAINLINE STATION 228+00 TO 248+00	10,761.02	8,608.82	1,779.40	6,829.41
MAINLINE STATION 248+00 TO 271+00	11,241.72	8,993.38	4,536.85	4,456.52
SCHOOL STREET	865.48	532.38	860.11	-327.73
EARTHWORK SUB-TOTAL	33,072.61	26,458.09	10,845.56	15,612.52
TEMPORARY EARTHWORK SUMMARY				
SOUTH SCHOOL STREET	776.85	621.48	477.78	143.70
NORTH SCHOOL STREET	82.41	65.93	95.37	-29.44
TEMPORARY EARTHWORK SUB-TOTAL	859.26	687.41	573.15	114.26
EARTHWORK AND TEMPORARY EARTHWORK SUB-TOTAL	33,931.87	27,145.49	11,418.71	15,726.78
TEMPORARY EARTHWORK TOTAL	33,932	27,145	11,419	15,727

PIPE CULVERT REMOVAL					
LOCATION				SIZE	FOOT
ILLINOIS ROUTE 8					
STA. 201+67.00	TO	STA. 202+66.00	RT	15"	99.5
STA. 204+21.30	TO	STA. 204+77.20	LT	15"	56.0
STA. 205+18.80	TO	STA. 205+76.60	RT	15"	58.0
STA. 209+76.20	TO	STA. 209+76.60	LT	48"	19.5
STA. 209+77.15	TO	STA. 209+77.20	LT/RT	2' BOX	56.0
STA. 214+16.35	TO	STA. 215+16.11	LT	3'x4'	100.0
STA. 215+01.00	TO	STA. 215+77.23	RT	12"	100.5
STA. 215+77.23	TO	STA. 215+77.24	LT/RT	3'x4'	58.0
STA. 217+13.40	TO	STA. 217+36.50	RT	21"	28.0
STA. 223+19.30	TO	STA. 223+77.80	RT	18"	59.0
STA. 223+67.40	TO	STA. 224+12.60	LT	18"	45.0
STA. 224+37.50	TO	STA. 224+91.48	RT	24"	54.5
STA. 224+91.48	TO	STA. 225+94.06	RT	24"	103.5
STA. 225+94.06	TO	STA. 226+12.70	RT	24"	36.0
STA. 227+01.80	TO	STA. 227+73.70	RT	12"	73.0
STA. 228+68.70	TO	STA. 229+10.80	RT	8"	43.0
STA. 229+89.10	TO	STA. 230+08.50	RT	15"	20.0
STA. 230+30.30	TO	STA. 230+66.00	RT	12"	36.0
STA. 231+10.90	TO	STA. 231+36.30	RT	15"	26.0
STA. 231+78.10	TO	STA. 232+17.40	RT	12"	40.0
STA. 232+00.60	TO	STA. 232+15.78	LT	24"	24.0
STA. 232+68.50	TO	STA. 232+92.68	LT/RT	28"	77.0
STA. 233+47.10	TO	STA. 233+65.30	RT	15"	18.5
STA. 233+76.00	TO	STA. 234+01.80	RT	15"	26.0
STA. 234+47.60	TO	STA. 235+06.70	RT	15"	59.5
STA. 235+46.80	TO	STA. 235+74.00	RT	15"	27.5
STA. 236+44.00	TO	STA. 236+77.20	RT	15"	33.5
STA. 236+68.00	TO	STA. 237+03.80	LT	15"	36.0
STA. 237+24.60	TO	STA. 239+51.40	RT	15"	227.0
STA. 237+79.00	TO	STA. 238+24.10	LT	15"	45.5
STA. 239+04.00	TO	STA. 239+24.30	LT	15"	20.5
STA. 239+80.40	TO	STA. 240+74.60	RT	15"	94.5
STA. 241+84.50	TO	STA. 242+30.00	RT	15"	45.5
STA. 242+36.00	TO	STA. 242+61.50	LT	12"	25.5
STA. 243+15.80	TO	STA. 243+59.40	RT	15"	44.0
STA. 243+65.90	TO	STA. 244+48.40	RT	15"	82.5
STA. 243+94.50	TO	STA. 244+67.80	LT	15"	73.5
STA. 244+65.80	TO	STA. 245+05.40	RT	15"	40.0
STA. 245+41.80	TO	STA. 246+03.00	RT	15"	61.5
STA. 245+85.70	TO	STA. 246+34.30	LT	15"	48.5
STA. 246+83.20	TO	STA. 247+09.60	RT	15"	26.5
STA. 248+07.00	TO	STA. 248+45.40	RT	15"	38.5
STA. 249+24.40	TO	STA. 249+58.50	LT	12"	34.5
STA. 249+47.40	TO	STA. 249+65.30	RT	15"	18.0
STA. 249+97.70	TO	STA. 250+22.10	RT	12"	24.5
STA. 250+27.10	TO	STA. 250+47.60	RT	15"	20.5
STA. 251+27.40	TO	STA. 251+46.50	RT	18"	19.5
STA. 251+41.10	TO	STA. 251+82.50	LT	18"	41.5
STA. 252+05.40	TO	STA. 252+52.10	RT	18"	47.0
STA. 252+27.20	TO	STA. 252+59.40	LT	12"	32.5
STA. 253+31.10	TO	STA. 253+59.70	RT	12"	28.5
STA. 253+84.10	TO	STA. 254+08.10	LT	12"	24.0
STA. 254+69.30	TO	STA. 254+91.66	RT	12"	22.5
STA. 255+78.80	TO	STA. 255+84.80	RT	12"	6.0
STA. 256+92.30	TO	STA. 257+64.80	RT	12"	73.0
STA. 257+36.10	TO	STA. 257+62.90	LT	12"	27.0
STA. 259+39.20	TO	STA. 259+81.70	RT	12"	43.0
STA. 264+58.50	TO	STA. 264+98.30	LT	18"	40.0
SCHOOL STREET					
STA. 4+65.00	TO	STA. 5+05.00	LT	12"	40.0
STA. 5+91.70	TO	STA. 6+20.80	LT	15"	30.0
STA. 7+27.80	TO	STA. 7+50.30	RT	12"	22.5
STA. 7+49.10	TO	STA. 8+33.50	LT	12"	84.5
STA. 11+50.10	TO	STA. 12+13.80	LT	15"	64.0
STA. 12+76.60	TO	STA. 12+78.20	LT/RT	15"	45.0
STA. 12+77.60	TO	STA. 12+78.50	LT	15"	27.0
				SUB-TOTAL	3,102.0
				TOTAL	3,102

SEGMENTAL CONCRETE BLOCK WALL				
LOCATION				SQ FT
ILLINOIS ROUTE 8				
STA. 201+30.50	TO	STA. 202+60.00	LT	477
			TOTAL	477

PAVEMENT AND SHOULDER REMOVAL					PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL
LOCATION					SQ YD	SQ YD	SQ YD
ILLINOIS ROUTE 8							
STA. 201+45.30		TO	STA. 206+00.00		2,108.0		
STA. 201+30.60	LT	TO	STA. 202+28.40	LT		22.5	
STA. 201+60.90	RT	TO	STA. 202+69.70	RT		355.0	
STA. 202+37.10	LT	TO	STA. 203+63.80	LT		261.5	
STA. 204+21.40	LT	TO	STA. 204+80.60	LT		151.5	
STA. 205+05.80	RT	TO	STA. 205+90.70	RT		196.0	
STA. 206+00.00		TO	STA. 212+00.00		2,408.0		
STA. 206+00.80	LT	TO	STA. 212+00.00	LT			191.5
STA. 206+87.30	RT	TO	STA. 207+90.10	RT		260.0	
STA. 207+87.60	RT	TO	STA. 212+00.00	RT			144.0
STA. 208+95.20	RT	TO	STA. 209+13.00	RT	22.0		
STA. 212+00.00		TO	STA. 218+00.00		2,803.5		
STA. 212+00.00	LT	TO	STA. 214+21.40	LT			71.0
STA. 212+00.00	RT	TO	STA. 214+13.90	RT			76.0
STA. 214+96.20	RT	TO	STA. 215+35.40	RT	28.0		
STA. 215+12.50	RT	TO	STA. 218+00.00	RT			116.5
STA. 215+14.30	LT	TO	STA. 218+00.00	LT			90.0
STA. 218+00.00		TO	STA. 224+00.00		2,388.0		
STA. 218+00.00	LT	TO	STA. 224+00.00	LT			200.0
STA. 218+00.00	RT	TO	STA. 224+00.00	RT			253.5
STA. 224+00.00		TO	STA. 230+00.00		2,557.5		
STA. 224+00.00	LT	TO	STA. 227+05.10	LT			96.5
STA. 224+00.00	RT	TO	STA. 224+28.10	RT			9.0
STA. 224+28.00	RT	TO	STA. 224+93.20	RT		333.5	
STA. 224+93.10	RT	TO	STA. 226+81.50	RT			103.0
STA. 227+71.90	RT	TO	STA. 230+00.00	RT			102.0
STA. 228+01.20	LT	TO	STA. 230+00.00	LT			104.5
STA. 228+69.80	RT	TO	STA. 229+07.00	RT		47.0	
STA. 230+00.00		TO	STA. 236+00.00		2,532.0		
STA. 230+00.00	LT	TO	STA. 236+00.00	LT			205.5
STA. 230+00.00	RT	TO	STA. 232+87.70	RT			119.5
STA. 233+43.30	RT	TO	STA. 233+95.20	RT		29.0	
STA. 234+59.40	RT	TO	STA. 235+06.80	RT		20.5	
STA. 235+48.70	RT	TO	STA. 235+70.50	RT		6.5	
STA. 236+00.00		TO	STA. 242+00.00		1,835.5		
STA. 236+00.00	LT	TO	STA. 236+63.10	LT			13.5
STA. 236+38.20	RT	TO	STA. 236+76.80	RT		90.5	
STA. 236+59.30	LT	TO	STA. 237+12.30	LT		86.5	
STA. 237+32.90	RT	TO	STA. 239+48.90	RT			76.0
STA. 237+74.80	LT	TO	STA. 238+29.00	LT		243.0	
STA. 238+32.40	RT	TO	STA. 239+31.80	RT		164.0	
STA. 239+01.30	LT	TO	STA. 239+25.40	LT		82.0	
STA. 242+00.00		TO	STA. 248+00.00		1,826.5		
STA. 244+53.10	RT	TO	STA. 244+67.60	RT		16.5	
STA. 245+43.10	RT	TO	STA. 246+08.60	RT		118.5	
STA. 245+76.60	LT	TO	STA. 246+41.10	LT		198.5	
STA. 246+84.20	RT	TO	STA. 247+11.10	RT		8.5	
STA. 248+00.00		TO	STA. 254+00.00		1,900.5		
STA. 249+46.20	RT	TO	STA. 249+68.70	RT		44.5	
STA. 249+99.50	RT	TO	STA. 250+20.20	RT		45.0	
STA. 250+28.30	RT	TO	STA. 250+45.60	RT		5.5	
STA. 251+23.50	RT	TO	STA. 251+46.20	RT		5.0	
STA. 251+32.70	LT	TO	STA. 251+82.20	LT		10.5	
STA. 254+00.00		TO	STA. 260+00.00		1,999.5		
STA. 254+70.40	RT	TO	STA. 254+94.40	RT		5.0	
STA. 256+96.80	RT	TO	STA. 257+14.60	RT		19.5	
STA. 257+18.10	LT	TO	STA. 257+70.90	LT		8.0	
STA. 259+32.00	RT	TO	STA. 260+00.00	RT			52.0
STA. 259+59.70	RT	TO	STA. 260+00.00	RT			7.0
STA. 260+00.00		TO	STA. 266+00.00		1,950.0		
STA. 260+00.00	RT	TO	STA. 266+00.00	LT			639.0
STA. 260+00.00	RT	TO	STA. 266+00.00	RT			643.5
STA. 266+00.00		TO	STA. 270+78.11		1,038.0		
STA. 266+00.00	LT	TO	STA. 270+78.11	LT			561.0
STA. 266+00.00	RT	TO	STA. 272+12.40	RT			484.0
SCHOOL STREET							
STA. 4+64.20	LT	TO	STA. 5+05.30	LT		52.5	
STA. 5+05.60		TO	STA. 9+80.20		1,379.5		
STA. 5+86.70	LT	TO	STA. 6+23.70	LT		92.5	
STA. 7+28.60	RT	TO	STA. 7+46.30	RT		16.5	
STA. 7+51.50	LT	TO	STA. 8+35.30	LT		168.0	
STA. 8+02.40	RT	TO	STA. 8+73.70	RT		107.0	
STA. 8+50.50	LT	TO	STA. 9+30.50	LT			70.0
STA. 9+86.10		TO	STA. 14+99.50		1,670.5		
STA. 11+20.45	LT	TO	STA. 12+37.38	LT		649.0	
STA. 14+21.60	LT	TO	STA. 14+57.10	LT		136.5	
				SUBTOTAL	28,447.0	4,056.0	4,428.5
				TOTAL	28,447	4,056	4,429

FILE NAME = x:\projects\200803566\dgn\D4-Rte8-sht-Schedule-1.dgn	USER NAME = IDOT	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 2.000 FT / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/21/2011	DATE - 10-21-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 399 (IL. RTE. 8)
SCHEDULE OF QUANTITES

SCALE: NONE | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36 R-7	TAZEWELL	390	20
		CONTRACT NO. 68370		
		ILLINOIS FED. AID PROJECT		